

MERIDIAN CENTRAL ESTATE - STAGE 29

BROWN PROPERTY GROUP

CITY OF CASEY

CONSTRUCTION NOTES

SITE MANAGEMENT

- A1. Prior to commencement of works on site, the contractor must ensure that all matters relating to the Occupational Health & Safety Act 2004, including all relevant regulations, have been addressed. In particular, the required notifications must be conveyed to the Victorian Workcover Authority - Health & Safety division with respect to trenching operations. Details of the contractors occupational health & safety procedures must be lodged with the superintendent prior to commencement of works.
- A2. All native trees & shrubs to be retained unless road construction necessitates their removal or removal is directed by the engineer. A town planning permit is required for the removal of native trees & / or vegetation. The removal or retention of any existing trees must be in accordance with the approved landscape plan, or else approval will be required from the City of Casey landscape approvals officer.
- A3. Existing dam or watercourses to be excavated to a firm base & backfilled as specified. Consulting engineer to be notified when the dam or watercourses are excavated to a firm base. No filling is to be placed prior to dams being inspected & levels taken. Backfilling is to be carried out to the satisfaction of the Council supervising engineer.
- A4. Prior to commencement of works, the contractor must submit a Site Management Plan (SMP) to the consultant for approval. The contractor must comply with the recommendations of the Environment Protection Authority publication No.275 "Construction techniques for sediment pollution control". Appropriate siltation control is to be maintained throughout the construction & maintenance period of the works.
- A5. Provide temporary safety barrier fence (Farm Fence as per MW Std Dwg 7251/4/203) along extent of outfall drain where the drain is greater than 1.5m in depth & side slopes are steeper than 1 in 3. Safety fence to remain until permanent underground drainage is installed.
- A6. Contractor to remove existing irrigation & drainage pipes & pits encountered on site. Trenches to be backfilled in accordance with notes C2 & C3.
- A7. An environmental management plan (EMP) must be submitted to and approved by Council prior to the commencement of any works on site and all works must be carried out in accordance with this EMP.
- A8. A traffic management plan (TMP) must be submitted to, and approved by Council prior to the commencement of any works on site and all traffic management must be carried out in accordance with this TMP.

GENERAL

- B1. All works to be carried out in accordance with AS2124-1992 general conditions of contract & the City of Casey and EDCM current specification & standard drawings & to the satisfaction of the City of Casey works supervisor.
- B2. Council to be notified two (2) clear days prior to commencement of works.
- B3. Before commencement of works on trenches in excess of 1.5m deep, the civil contractors construction supervisor must give notice in writing of such proposals to Worksafe Victoria in accordance with Part 5.1, Division 4 of the Occupational Health & Safety regulations (2007) & undertake safety precautions in trenching operations in accordance with Workcover's code of practice (1988).
- B4. Lots to be graded (1 in 150 min slope) & left clean to the satisfaction of the engineer. Finished levels to be compatible with lots adjoining this stage.
- B5. On completion the contractor is responsible for the removal of all rubbish & spoil from site. No surplus trees, vegetation or other material is to be burnt on site.
- B6. Reserves to be free draining & to be left in a condition satisfactory to the City of Casey works supervisor.
- B7. Where works are in the vicinity of existing services these services are to be located & the various authorities notified prior to the commencement of works.
- B8. All TBM's & control points are to be maintained & protected at all times during construction. Should any marks be disturbed, the contractor will immediately notify the consultant to arrange re-instatement at the contractors expense.
- B9. Provide painted paling fence along any boundary common to lots & municipal reserves as per Council Std. Dwg. S-706. Paling to be on the reserve side.
- B10. As constructed plans and electronic asset information in D-Spec and R-Spec format must be submitted to Council prior to practical completion.

ROADWORKS

- C1. 100a agricultural pipe drains (MPA standard drawing EDCM 202) to be placed behind all kerb & channel & buffer pitchers & where directed by the engineer.
- C2. Filling in all properties & road reserves is to be carried out using approved clay fill. Top soil & all vegetable matter to be stripped from site prior to filling. All filling to be carried out in accordance with AS3796-2007 and the geotechnical report. Level 1 inspection and testing to be carried out in accordance with AS3798-2007 Section 8.2. A fill report must be submitted to the Consultant, showing from a NATA registered soil testing laboratory.
- C3. Importing Fill: All imported fill must be tested by a NATA approved laboratory to ensure it is suitable for use on site, & any contaminants are within accepted levels. Under no circumstances should fill material enter or leave the site without the permission of the supervising engineer & Council works supervisor, prior to it being appropriately tested. All vehicles transporting fill material to & from the site must have appropriate measures in place to ensure that material does not get onto roads & into stormwater systems & natural waterways.
- C4. Batters to be 1 in 5 for fill & 1 in 3 for cut unless noted otherwise.
- C5. Cut batters are to be grassed & mulched with a mixture of chopped grass, straw & bitumen emulsion.
- C6. Where cut batters exceed 700mm an additional 300mm berm shall be formed behind footpath.

- C7. Access ramps are to be constructed where cut batters exceed 1.0m. They are to be graded 1 in 10 for the first 2.5m from the back of path & then at a maximum of 1 in 4 to natural surface.
- C8. The water conduit offset from the lot boundary is given on the water reticulation plan. The contractor must construct conduits to accord with the given offset & ensure that the concrete marks the kerb & footpath exactly above the conduit.
- C9. Irrigation conduits are to be DN100 DWV PVC installed beneath the pavement and/or capping layer, if present. Locations are to be marked using a green dot spray painted on the top of kerb.
- C10. All footpaths are to be 125mm thick 25MPa concrete with SL72 mesh centrally located in accordance with the MPA standard drawing EDCM 401.
- C11. NBN Co to be notified seven (7) days prior to concrete works being placed.
- C12. Electrical distribution pits within footpaths are to be a minimum of 300mm within the edge of the path. Concrete is to be placed around distribution pits to a minimum depth of 200mm.
- C13. All street signs to be constructed & erected to current City of Casey standards including logo. Court street names are to show court name only.
- C14. Traffic control signs, markings & delineators to be installed in accordance with AS1742.2. All line marking is to be long life road marking, with longitudinal lines in thermoplastic & transverse markings in cold applied.
- C15. Driveways to be constructed in accordance with the MPA standard drawings EDCM 501 & EDCM 502. Single driveways to be a minimum 3.5m wide & to be offset 0.75m from side boundary or easement unless otherwise shown.
- C16. Kerb transition to take place in the minor street over a 2.0m length from either the tangent point or TP pit.
- C17. Existing road works to be reconstructed as required to provide, without discontinuity, a connection in accordance with design levels & grades.
- C18. Provide 2.5m wide shared footpath through reserves as shown on a curvilinear alignment to the satisfaction of the engineer.
- C19. Tactile ground surface indicators (TGSIs) are to be installed at all pram crossings & pedestrian cross points in accordance with AS1428.4 : 2002 & MPA standard drawing EDCM 403.
- C20. If any existing substandard filling is encountered on the site it must be removed and replaced with approved fill material properly compacted to Council requirements. A geo-technical report must be submitted showing details of depth, type of material and density of the fill areas concerned.

DRAINAGE

- D1. Drainage & pits to be set out from offsets shown rather than from centreline pipe chainages. Centreline of pits at TP's to be offset 1.00m.
- D2. Terra Firma or fibreglass type pit lids are required for all drainage pits & all grates for pits are to be Class D, to comply with AS3996 unless otherwise shown. All drainage works are to be constructed to council specifications.
- D3. All pipes up to and including 750mm in diameter shall be rubber ring jointed (RRJ). Pipes above this size may be flush jointed with external sealing bands. For pipes greater than 900mm and changes in direction between 2 connecting pipes exceeding 10° construct segmented curves using splayed pipes with banded joints, having deflections within the manufacturer's specification.
- D4. All pipes to be Class 2' R.C. rubber ring joint unless noted otherwise. PVC pipes to be Class SH unless specified.
- D5. Pipe trenches beneath the road pavement, footpath or within 150mm of the kerb & channel to be backfilled with 20mm Class 3 FCR in 150mm layers.
- D6. Property inlets to be constructed as per MPA standard drawing EDCM 701 – EDCM 704.
- D7. All proposed drainage stubs to be blanked off at end of pipe with timber planks to the satisfaction of the supervising engineer.
- D8. A CCTV report must be provided for all drainage lines prior to issue of practical completion.

PAVEMENT

- E1. Modification of the pavement requires approval by the City of Casey works supervisor.

DRAWING INDEX

DRAWING No.	TITLE	REVISION
1801767-29-001	COVER SHEET	A
1801767-29-002	TYPICAL ROAD CROSS SECTIONS & GENERAL DETAILS	A
1801767-29-003	RETAINING WALL DETAILS	A
1801767-29-010	LAYOUT PLAN	A
1801767-29-015	INTEGRATED WATER MANAGEMENT LAYOUT PLAN	A
1801767-29-016	INTEGRATED WATER MANAGEMENT DETAILS (SHEET 1 OF 2)	A
1801767-29-017	INTEGRATED WATER MANAGEMENT DETAILS (SHEET 2 OF 2)	A
1801767-29-100	ROAD LONGITUDINAL SECTIONS - PORTOBELLO BOULEVARD	A
1801767-29-200	ROAD CROSS SECTIONS - PORTOBELLO BOULEVARD (SHEET 1 OF 2)	A
1801767-29-201	ROAD CROSS SECTIONS - PORTOBELLO BOULEVARD (SHEET 2 OF 2)	A
1801767-29-350	SIGNAGE & LINE MARKING PLANS	A
1801767-29-400	DRAINAGE LONGITUDINAL SECTIONS AND PIT SCHEDULE	A


Survey Origin:

Coordinates are on a local plane datum based upon MGA2020 Zone 55 bearings and truncated MGA2020 Zone 55 co-ordinates at PM77. Heights are to AHD vide Permanent Mark PM 56 (Cranbourne) RL 26.71 Bearing Datum is MGA2020 Zone 55 which has been derived by our GPSnet Survey.

Plane Grid Coordinates to MGA2020 Zone 55 Grid Coordinates

Conversion:

(PLANE SHIFT) Add + 353,823.586 to Eastings
Add +5,780,840.520 to Northings
(APPLY SCALE FACTOR) Scale by 0.999846 at point PM77



SITE PLAN

NOT TO SCALE

MELWAY REF: 135 F3

ISSUED
FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date K. PHAM 05.05.2021
Drawn N. TABUENA
Approved Date M. FELICIANO 11.06.2021
PS Number PS842534P













Project Details MERIDIAN CENTRAL ESTATE
STAGE 29
CITY OF CASEY
Drawing Title COVER SHEET

Sheet 01 of 12

Scale

Project Ref 1801767
Stage No 29
Drawing No 001
Rev A





NOTES
1. REFER TO EDCM 502 FOR FURTHER DETAILS
8.0m DOUBLE VEHICLE CROSSING DETAIL
NOT TO SCALE

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					




Designed Date: K. PHAM 05.05.2021
Drawn: N. TABUENA
Approved Date: M. FELICIANO 11.06.2021
PS Number: PS942534P

BW Beveridge Williams
1 Glenferrie Road
Malvern VIC 3144
ph: 03 9524 8888
www.beveridgewilliams.com.au

Project Details: MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY
Drawing Title: TYPICAL ROAD CROSS SECTIONS & GENERAL DETAILS


Sheet 02 of 12	
Project Ref: 1801767	Stage No: 29
Drawing No: 002	Rev: A





MASS ROCK RETAINING WALL SCHEDULE

MAX WALL HEIGHT-H(mm)	FOUNDING DEPTH-D(mm)	BASE WIDTH - B(mm)	FRONT FACE SETBACK-S (mm)	CREST WIDTH-C(mm)
400	400	450	15	300
500	400	500	15	300
600	400	500	30	300
800	400	600	30	300
1000	400	700	30	300

- RETAINING WALL NOTE R.1
 a. WHERE FOOTPATH ABUTS RETAINING WALL CONTINUE CONCRETE UP TO BASE OF RETAINING WALL.
- FOOTING NOTE F.2
 a. TOE OF WALL SHALL PENETRATE THROUGH ANY FILL MATERIAL & THE NATURAL SILT SOILS TO BE FOUNDED AT LEAST 100mm INTO THIS UNDERLYING NATURAL STILL CLAY OR WEATHERED ROCK. ALL EXCAVATIONS SHALL HAVE FOUNDED DEPTHS AND BEARING CAPACITY APPROVED BY THE ENGINEER OR BUILDING SURVEYOR BEFORE CONCRETE IS PLACED.
 FOOTING EXCAVATIONS WHICH ARE DEEPEO TO PENETRATE THROUGH UNSUITABLE SOILS SHALL BE BACKFILLED UP TO UNDERSIDE OF FOOTINGS WITH 15 MPa BLINDING CONCRETE.
 b. ALL EXCAVATION FOUNDING SURFACES SHALL BE LEVEL (NOT INCLINED) CLEAN CUT & FREE OF MUD OR WATER.
 c. ALL SEEPAGE INFLOW SHALL BE REMOVED BEFORE PLACEMENT OF CONCRETE.
 d. FOOTINGS SHALL BE FOUNDED IN STIFF NATURAL CLAY HAVING A SAFE BEARING CAPACITY OF 150kPa.



MASS ROCK RETAINING WALL DETAIL WITH PALING TIMBER FENCE (TYPE RR) OR BOLLARD (BOLLARD BY LANDSCAPE) NTS



CONCRETE SLEEPER RETAINING WALL SCHEDULE

HEIGHT - H(mm)	DEPTH - D(mm)	SOLDIERS SIZE @ 2.4m CTS
600	900	100 UC 14.8
800	1200	100 UC 14.8
1000	1500	100 UC 14.8

Dmin TO BE GREATER OF THAT SHOWN ABOVE OR 1000mm BELOW ADJACENT SEWER / DRAINAGE

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
 Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
 No unauthorised copying is permitted


REV	DESCRIPTION	DATE	DRN	APP	REV	DESCRIPTION	DATE	DRN	APP
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date: K. PHAM 05.05.2021
 Drawn: N. TABUENA
 Approved Date: M. FELICIANO 11.06.2021
 PS Number: PS942534P

BW Beveridge Williams
 1 Glenferrie Road
 Malvern VIC 3144
 ph: 03 9524 8888
 www.beveridgewilliams.com.au

Project Details	MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY	Sheet 03 of 12
Drawing Title	RETAINING WALL DETAILS	Scale
Project Ref	1801767	Stage No
	29	Drawing No
	003	Rev
		A



LEGEND - LAYOUT PLAN

- STORMWATER DRAIN, PIT & PROPERTY INLET
- MELBOURNE WATER DRAIN & PIT
- SWALE DRAIN
- SEWER & MAINTENANCE STRUCTURES
- HOUSE DRAIN
- SERVICE CONDUITS
- TACTILE PAVERS (INDICATIVE ONLY)
- ELECTRICITY (UNDERGROUND)
- ELECTRICITY (OVERHEAD)
- OPTIC FIBRE
- TELECOMMUNICATIONS
- GAS
- WATER
- RECYCLED WATER
- EXISTING ELECTRICITY (UNDERGROUND)
- EXISTING ELECTRICITY (OVERHEAD)
- EXISTING GAS
- EXISTING OPTIC FIBRE
- EXISTING TELECOMMUNICATIONS
- EXISTING WATER
- EXISTING RECYCLED WATER
- EXISTING STORMWATER DRAIN
- EXISTING MELBOURNE WATER DRAIN
- EXISTING SEWER
- EXISTING HOUSE DRAIN
- EXISTING SWALE DRAIN
- EXISTING SURFACE LEVEL
- FINISHED BUILDING LINE LEVEL
- FINISHED RIDGE LINE LEVEL
- TOP OF RETAINING WALL
- BOTTOM OF RETAINING WALL
- RIDGE LINE
- MASS ROCK RETAINING WALL
- CONCRETE SLEEPER RETAINING WALL
- EXISTING CONCRETE SLEEPER RETAINING WALL
- ZERO LOT LINES
- PAVEMENT TREATMENT
- STRUCTURAL FILL > 200mm DEEP
- EX. STRUCTURAL FILL > 200mm DEEP
- DIRECTION OF FALL
- OVERLAND FLOW
- ALLOTMENT TO BE GRADED EVENLY IN
- DIRECTION OF FALL TO LEVELS INDICATED
- CONCRETE EDGE STRIP WITH SUBSOIL DRAIN
- "NO ROAD" SIGN & BARRIER
- LIMIT OF WORKS
- EXISTING TREE TO BE REMOVED
- PERMANENT SURVEY MARK
- TEMPORARY BENCH MARK
- PROPOSED DRIVEWAY
- TREE PROTECTION ZONE (TPZ)

ROAD LAYOUT TABLE

Road Name	Reserve Width (m)	Road Width (m)			Kerb Type		Verge Width (m)	
		Lip to Lip	Inv to Inv	Back to Back	North	South	North	South
PORTOBELLO BOULEVARD	20.00	9.70 / 5.10	10.60 / 6.00	10.90 / 6.30	600 B2	600 B2	4.70 / 7.00	4.70 / 7.00

SERVICE OFFSET TABLE

Location	Gas		ND - Water		Water		Electricity		Telecommunication		Lighting	
	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)
PORTOBELLO BOULEVARD	N	2.00	N	2.45	N	2.95	S	2.60	S	1.90	BOK	0.80

NOTE: STREET TREES ARE TO BE PLANTED IN THE CENTRE OF ALL NATURE STRIPS

WARNING
BWARE OF UNDERGROUND SERVICES
 The locations of underground services are approximate only and their exact position should be proven on site.
 No guarantee is given that all existing services are shown. Locate all underground services before commencement of works.
DIAL 1100 BEFORE YOU DIG
 www.1100.com.au

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					

BROWN PROPERTY GROUP

M MERIDIAN CENTRAL

0 5 10 20 30 40
 SCALE 1:500 AT A1 SIZE

Designed Date: K. PHAM 05.05.2021
 Drawn: N. TABUENA
 Approved Date: M. FELICIANO 11.06.2021
 PS Number: PS842534P

BW Beveridge Williams
 1 Glenferrie Road
 Malvern VIC 3144
 ph: 03 9524 8888
 www.beveridgewilliams.com.au

Project Details: MERIDIAN CENTRAL ESTATE
 STAGE 29
 CITY OF CASEY


Drawing Title: LAYOUT PLAN

Sheet 04 of 12


Scale: 1:500 @ A1

Project Ref: 1801767
 Stage No: 29
 Drawing No: 010
 Rev: A

K:\Jobs Data\1801767 - Meridian_Eng\Stage 29 Drawings\1801767-29-010-LAY.dwg




- LEGEND - LAYOUT PLAN**
- STORMWATER DRAIN, PIT & PROPERTY INLET
 - MELBOURNE WATER DRAIN & PIT
 - SWALE DRAIN
 - SEWER & MAINTENANCE STRUCTURES
 - HOUSE DRAIN
 - SERVICE CONDUITS
 - E ELECTRICITY (UNDERGROUND)
 - OH E ELECTRICITY (OVERHEAD)
 - O OPTIC FIBRE
 - T TELECOMMUNICATIONS
 - G GAS
 - DW WATER
 - NDW RECYCLED WATER
 - Ex E EXISTING ELECTRICITY (UNDERGROUND)
 - Ex OH E EXISTING ELECTRICITY (OVERHEAD)
 - Ex G EXISTING GAS
 - Ex DW EXISTING WATER
 - Ex NDW EXISTING RECYCLED WATER
 - EXISTING STORMWATER DRAIN
 - EXISTING SEWER
 - EXISTING HOUSE DRAIN
 - EXISTING SWALE DRAIN
 - MASS ROCK RETAINING WALL
 - CONCRETE SLEEPER RETAINING WALL
 - LIMIT OF WORKS
 - EXISTING TREE TO BE REMOVED
 - PROPOSED DRIVEWAY
 - RAINGARDEN
 - 1000 SLOPPED PVC PIPE



INSET A

SCALE 1:50 AT A1 SIZE



INSET B

SCALE 1:50 AT A1 SIZE

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted.						
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF		
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION



Designed Date: K. PHAM 05.05.2021
 Drawn: N. TABUENA
 Approved Date: M. FELICIANO 11.06.2021
 PS Number: PS842534P





Project Details: MERIDIAN CENTRAL ESTATE
 STAGE 29
 CITY OF CASEY
 Drawing Title: INTERGATED WATER MANAGEMENT DETAILS
 (SHEET 1 OF 3)

Sheet 05 of 12			
Scale			
Project Ref	Stage No	Drawing No	Rev
1801767	29	015	A



K:\Jobs Data\1801767 - Meridian_Eng\Stage 29 Drawings\1801767-29-015-IMMS.dwg



BIORETENTION NOTES

The Bioretention system will operate so that water will infiltrate into the filter media and move vertically through the profile. The Bioretention system requires three layers of media:

1. Filter
2. Transition
3. Drainage

1. FILTER LAYER

600mm depth of material meeting the specifications outlined in CRC for Water Sensitive Cities 'Adoption Guidelines for Stormwater Biofiltration Systems' (July 2015), Appendix C, Table 1.

- Filter media must meet the following specifications:
- Material - to be either a washed, well-graded sand, or naturally occurring sand meeting the required specifications.
 - Hydraulic Conductivity - 100-300mm/hr
 - Clay & Silt Content - < 3% (w/w)
 - Smooth Grading - all particle sizes represented across sieve sizes; see also particle size distribution below.
 - Nutrient Content - low nutrient content with Total Nitrogen (TN) < 1000 mg/kg, and available phosphate (Colwell) < 80 mg/kg
 - Organic Matter Content - minimum content ≤ 5% to support vegetation
 - pH - 5.5-7.5, as specified for 'natural soils and soil blends' in AS4419 - 2003 (pH 1.5 in water)
 - Electrical conductivity < 1.2 dS/m, as specified for 'natural soils and soil blends' in AS4419 - 2003
 - Horticultural suitability - media must be capable of supporting healthy vegetation

Particle Size Distribution of selected filter media to be as follows:

(% w/w)	Retained
Clay & Silt	<3% (<0.05 mm)
Very Fine Sand	5-30% (0.05-0.15 mm)
Fine Sand	10-30% (0.15-0.25 mm)
Medium Sand	40-60% (0.25-0.5 mm)
Coarse Sand	7-10% (0.5-1.0 mm)
Very Coarse Sand	0-10% (1.0-2.0mm)
Fine Gravel	<3% (2.0-3.4 mm)

The Filter media should contain some organic matter for increased water holding capacity but be low in nutrient content. Also the media should be free of rubbish, deleterious material, toxicants and local weeds (as listed in local guidelines/ acts) and should not be hydrophobic.

2. TRANSITION LAYER

100mm depth of material meeting the specifications outlined in CRC for Water Sensitive Cities 'Adoption Guidelines for Stormwater Biofiltration Systems' (July 2015), Appendix C, Table 1.

- Transition layer material must meet the following specifications:
- Material - to be a clean, well-graded sand
 - Hydraulic Conductivity - must be higher than the hydraulic conductivity of the overlying filter media
 - Fine Particle Content - < 2%


Particle Size Distribution of the selected transition layer material must meet bridging criteria, the smallest 15% of sand particles must bridge with the largest 15% of filter media particles:

$D_{15} \text{ (transition layer)} \leq 5 \times D_{85} \text{ (filter media)}$

3. DRAINAGE LAYER

150mm depth of material meeting the specifications outlined in CRC for Water Sensitive Cities 'Adoption Guidelines for Stormwater Biofiltration Systems' (July 2015), Appendix C, Table 1.

- Transition layer material must meet the following specifications:
- Material - to be clean, fine aggregate, 2-7mm washed screenings (not scoria or quartz)
 - Hydraulic Conductivity - must be higher than the hydraulic conductivity of the overlying transition layer



Particle Size Distribution of the selected drainage layer material must meet bridging criteria; the smallest 15% of drainage layer particles must bridge with the largest 15% of transition layer particles:

$D_{15} \text{ (drainage layer)} \leq 5 \times D_{85} \text{ (transition layer)}$

Perforations in subsoil drainage must be small enough relative to the drainage layer material.

$D_{85} \text{ (drainage layer)} > \text{diameter subsoil drain pipe perforation}$

4. TEMPORARY FILTER LAYER

A layer of 75mm topsoil preferred / 50mm stone aggregate of 5-13mm, no fines

5. TESTING REQUIREMENTS

Testing to confirm Hydraulic Conductivity of the media under various levels of compaction shall be conducted using the ASTM F1815-06 Method.

Test imported topsoils and submit test results for approval at least 5 working days in advance of carting. In addition, the contractor is to supply a 500 gram sample of the filter medium to the superintendent for approval prior to purchasing bulk material.

The following tests are to be conducted to determine the suitability of selected media. The test results are to be submitted to the superintendent with Hydraulic Conductivity results for approval before placing bulk orders:

- Particle Size Distribution (PSD)
- AS4419-2003 - Soil properties for landscaping and garden use - Sandy Loam
- Saturated Hydraulic Conductivity
- Water holding capacity, where PSD does not meet specifications but silt and clay is <12%
- PH

Where a supplier can provide PSD and/or AS4419-2003 test results for the specific batch of media being purchased these will be accepted at the superintendents discretion.

6. INSTALLATION

Filter media shall be lightly compacted during installation to prevent migration of fine particles.

A single pass with a vibrating plate or roller machinery (e.g. a drum lawn roller) should be used to compact the filter media. Under no circumstances should heavy compaction or multiple passes be made. Filter media is to be installed near the completion of works to ensure the media quality is not affected due to ongoing construction works.

7. MAINTENANCE

Field testing of hydraulic Conductivity shall be carried out at three points within the system at one month following commencement of operation and in the second year of operation to assess the impact of vegetation on Hydraulic Conductivity. Weed management will need to be done manually until such time that the design vegetation is established with sufficient density to effectively prevent weed propagation.

8. TEMPORARY FILTER CLOTH

Surface of Filtration media to be covered with a temporary filter cloth (Bidim or Similar). Temporary Filter cloth to be removed and planting of the Bioretention Basin undertaken in accordance with the landscape plans once the building phase within the catchment is 80 - 90% complete.

9. COLLECTION (AG) PIPES

Collection pipes to be 100 dia. PVC SN6 (i.e. Sewer Grade), slotted with 2mm width slots. Minimum slot length = 1.2m of slot per lineal metre of pipe. Slotting can be undertaken by Central Pipe Fabrication or similar companies.

WARNING
Beware of Underground Services

The locations of underground services are approximate only and their exact position should be proven on site. No guarantee is given that all existing services are shown. Locate all underground services before commencement of works

DIAL 1100 BEFORE YOU DIG

www.1100.com.au

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted									
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.

BROWN PROPERTY GROUP

M MERIDIAN CENTRAL

Designed	K. PHAM
Date	05.05.2021
Drawn	N. TABUENA
Approved	M. FELICIANO
Date	11.06.2021
PS Number	PS842534P



BW Beveridge Williams

1 Glenferrie Road
Malvern VIC 3144
ph: 03 9524 8888
www.beveridgewilliams.com.au

Project Details	MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY
Drawing Title	INTERGATED WATER MANAGEMENT DETAILS (SHEET 2 OF 3)

Sheet 06 of 12			
Scale			
Project Ref	1801767	Stage No	29
Drawing No	016	Rev	A





WARNING
Beware of Underground Services
The locations of underground services are approximate only and their exact position should be proven on site. No guarantee is given that all existing services are shown. Locate all underground services before commencement of works.
DIAL 1100 BEFORE YOU DIG
www.1100.com.au

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date: 05.05.2021
Drawn: N. TABUENA
Approved Date: 11.06.2021
PS Number: PS942534P


BW Beveridge Williams
1 Glenferrie Road
Malvern VIC 3144
ph: 03 9524 8888
www.beveridgewilliams.com.au

Project Details: MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY
Drawing Title: INTERGATED WATER MANAGEMENT DETAILS (SHEET 3 OF 3)

Sheet 07 of 12
Scale: _____
Project Ref: 1801767
Stage No: 29
Drawing No: 017
Rev: A



	EXISTING SURFACE
	DESIGN LINE
	EXISTING SURFACE AT SOUTH BOUNDARY
	SOUTH LIP OF KERB
	EXISTING SURFACE AT NORTH BOUNDARY
	NORTH LIP OF KERB




VERTICAL GEOMETRY
HORIZONTAL GEOMETRY
DATUM RL36
DESIGN CENTRELINE
RIGHT LIP OF KERB
EXISTING SURFACE AT RIGHT BOUNDARY
LEFT LIP OF KERB
EXISTING SURFACE AT LEFT BOUNDARY
EXISTING SURFACE
CHAINAGE

PORTOBELLO BOULEVARD LONGITUDINAL SECTION

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date
Drawn
Approved Date
PS Number









BW Beveridge Williams
1 Glenferrie Road
Malvern VIC 3144
ph: 03 9524 8888
www.beveridgewilliams.com.au

Project Details
MERIDIAN CENTRAL ESTATE
STAGE 29
CITY OF CASEY
Drawing Title
ROAD LONGITUDINAL SECTIONS
PORTOBELLO BOULEVARD

Sheet 08 of 12			
Scale 1:500 H 1:50 V @ A1			
Project Ref 1801767	Stage No 29	Drawing No 100	Rev A

STRUCTURAL FILL REQUIRED UNDER PAVEMENT AND FOOTPATHS WHERE CONSTRUCTED ABOVE NATURAL SURFACE. REFER GEOTECH REPORT FOR SPECIFICATION


LEGEND		
NBL	NORTH BUILDING LINE	--- EXISTING SURFACE
SBL	SOUTH BUILDING LINE	— DESIGN SURFACE
EBL	EAST BUILDING LINE	▨ STRUCTURAL FILL
WBL	WEST BUILDING LINE	



ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date: K. PHAM 05.05.2021
Drawn: N. TABUENA
Approved Date: M. FELICIANO 11.06.2021
PS Number: PS842534P





Project Details: MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY
Drawing Title: ROAD CROSS SECTIONS PORTOBELLO BOULEVARD (SHEET 1 OF 2)

Sheet 09 of 12	
Scale: 1:100 H 1:50 V @ A1	
Project Ref: 1801767	Stage No: 29
Drawing No: 200	Rev: A


K:\Jobs Data\1801767 - Meridian\Eng\Stage 29\Drawings\1801767-29-200-RXS.dwg

STRUCTURAL FILL REQUIRED UNDER PAVEMENT AND FOOTPATHS WHERE CONSTRUCTED ABOVE NATURAL SURFACE. REFER GEOTECH REPORT FOR SPECIFICATION


LEGEND		
NBL	NORTH BUILDING LINE	--- EXISTING SURFACE
SBL	SOUTH BUILDING LINE	— DESIGN SURFACE
EBL	EAST BUILDING LINE	 STRUCTURAL FILL
WBL	WEST BUILDING LINE	




CH 639.975




CH 624.895




TPCH 616.427



TPCH 612.470



CH 669.757




CH 655.975

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					




Designed Date: K. PHAM 05.05.2021
Drawn: N. TABUENA
Approved Date: M. FELICIANO 11.06.2021
PS Number: PS842534P



Project Details: MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY
Drawing Title: ROAD CROSS SECTIONS PORTOBELLO BOULEVARD (SHEET 2 OF 2)


Sheet 10 of 12
Scale: 1:100 H 1:50 V @ A1
Project Ref: 1801767 Stage No: 29 Drawing No: 201 Rev: A



- NOTES**
- RRPM'S AT MAX 6m SPACING.
 - LINEMARKING TO BE EXTENDED AT LEAST 6m FROM THE TANGENT POINT
 - LINEMARKING IN ACCORDANCE WITH AS1742.
 - TGSI TO BE INSTALLED IN ACCORDANCE WITH VICROADS RDN 06-06 - JULY 2010
 - ALL STREET NAME SIGNS AT INTERSECTIONS TO INCLUDE RELEVANT STREET NUMBERING.
 - ALL LINE MARKING PAINT SHALL BE LONG LIFE TYPE. LATERAL WORKS AND ARROWS BEING COLD APPLIED PLASTIC TROWELLED INTO PLACE (MATERIAL DEGADUR PASTELINE) AND LONGITUDINAL LINES BEING EXTRUDED THERMOPLASTIC MATERIAL.

**ISSUED
FOR CONSTRUCTION**

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date: K. PHAM 05.05.2021
 Drawn: N. TABUENA
 Approved Date: M. FELICIANO 11.06.2021
 PS Number: PS942534P



BW Beveridge Williams
 1 Glenferrie Road
 Malvern VIC 3144
 ph: 03 9524 8888
 www.beveridgewilliams.com.au

Project Details: MERIDIAN CENTRAL ESTATE
 STAGE 29
 CITY OF CASEY
 Drawing Title: SIGNAGE & LINE MARKING PLAN

Sheet 11 of 12
 Scale: 1:500 @ A1
 Project Ref: 1801767 Stage No: 29 Drawing No: 350 Rev: A



PIT SCHEDULE											
PIT NO.	PIT TYPE	INTERNAL DIMENSION		INLET		OUTLET		PIT		STD DWG.	REMARKS
		WIDTH (mm)	LENGTH (mm)	DIAMETER (mm)	INVERT LEVEL (mm)	DIAMETER (mm)	INVERT LEVEL (mm)	INVERT RL	DEPTH (m)		
Ex11	EXISTING PIT	750	900	300	38.826			40.625	1.999		CONNECT TO EXISTING PIT
1	GRATED ENTRY PIT	600	900			300	39.258	40.658	1.400	EDCM 601	
Ex12	EXISTING PIT	750	900	300	39.375			41.044	1.869		CONNECT TO EXISTING PIT
2	GRATED PIT	600	900			300	39.544	41.044	1.500	EDCM 605	INSTALL 600 x 900 ECO-WEAVED FLAT GRATE OR APPROVED EQUIVALENT
Ex13	EXISTING PIT	750	900	300	40.091			41.609	1.718		CONNECT TO EXISTING PIT
3	GRATED ENTRY PIT	600	900			300	40.203	41.603	1.400	EDCM 601	
Ex21	EXISTING PIT	600	900	300	38.835			39.964	1.129		CONNECT TO STUB
4	JUNCTION PIT	600	900	300	39.610	300	39.560	40.630	1.070	EDCM 605	
5	JUNCTION PIT	600	900	300	40.100	300	40.050	41.070	1.020	EDCM 605	
EP1	END PIPE					300	40.520	41.492	0.972		CAP PIPE FOR FUTURE CONNECTION




NOTES:
ALL STORMWATER DRAINS UP TO AND INCLUDING 750mm DIA. ARE TO BE CLASS 2 R.R.J. PIPES UNLESS NOTED OTHERWISE.

LEGEND	
	EXISTING SURFACE
	DESIGN SURFACE
	DRAINAGE PIPE/PIT
	EXISTING DRAINAGE PIPE/PIT
	HYDRAULIC GRADE LINE
	NOTES 20mm CLASS 3 FCR BACKFILL

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
A	ISSUED FOR CONSTRUCTION	07.09.21	KP	MF					



Designed Date: K. PHAM 05.05.2021
 Drawn: N. TABUENA
 Approved Date: M. FELICIANO 11.06.2021
 PS Number: PS942534P



Project Details: MERIDIAN CENTRAL ESTATE STAGE 29 CITY OF CASEY
 Drawing Title: DRAINAGE LONGITUDINAL SECTIONS AND PIT SCHEDULE

Sheet 12 of 12
 Scale: 1:500 H 1:50 V @ A1
 Project Ref: 1801767 Stage No: 29 Drawing No: 400 Rev: A