MERIDIAN CENTRAL ESTATE - STAGE 35

BROWN PROPERTY GROUP CITY OF CASEY

CONSTRUCTION NOTES

SITE MANAGEMENT

- Prior to commencement of works on site, the contractor must ensure that all matters relating to the Occupational Health & Safety Act 2004, including all relevant regulations, have been addressed. In particular, the required notifications must be conveyed to the Victorian Workcover Authority Health & Safety division with respect to trenching operations. Details of the contractors occupational health & safety procedures must be lodged with the superintendent prior to commencement of works.
- A2. All native trees & shrubs to be retained unless road construction necessitates their removal or removal is directed by the engineer A town planning permit is required for the removal of native trees & / or vegetation. The removal or retention of any existing trees must be in accordance with the approved landscape plan, or else approval will be required from the City of Casey landscape
- Existing dam or watercourses to be excavated to a firm base & backfilled as specified. Consulting engineer to be notified when the dam or watercourses are excavated to a firm base. No filling is to be placed prior to dams being inspected & levels taken Backfilling is to be carried out to the satisfaction of the Council supervising engineer.
- Prior to commencement of works, the contractor must submit a Site Management Plan (SMP) to the consultant for approval. The contractor must comply with the recommendations of the Environment Protection Authority publication No.275 "Construction techniques for sediment pollution control". Appropriate silitation control is to be maintained throughout the construction &
- Provide temporary safety barrier fence (Farm Fence as per MW Std Dwg 7251/4/203) along extent of outfall drain where the drain is greater than 1.5m in depth & side slopes are steeper than 1 in 3. Safety fence to remain until permanent underground drainage
- An environmental management plan (EMP) must be submitted to and approved by Council prior to the commencement of any works on site and all works must be carried out in accordance with this EMP.
- A traffic management plan (TMP) must be submitted to, and approved by Council prior to the commencement of any works on site and all traffic management must be carried out in accordance with this TMP.

- All works to be carried out in accordance with AS2124-1992 general conditions of contract & the City of Casey and EDCM current
- Before commencement of works on trenches in excess of 1.5m deep, the civil contractors construction supervisor must give notice in writing of such proposals to Worksafe Victoria in accordance with Part 5.1, Division 4 of the Occupational Health & Safety regulations (2007) & undertake safety precautions in trenching operations in accordance with Workcover's code of practice (1988).
- Lots to be graded (1 in 150 min slope) & left clean to the satisfaction of the engineer. Finished levels to be compatible with lots
- On completion the contractor is responsible for the removal of all rubbish & spoil from site. No surplus trees, vegetation or other material is to be burnt on site.
- Reserves to be free draining & to be left in a condition satisfactory to the City of Casey works supervisor.
- Where works are in the vicinity of existing services these services are to be located & the various authorities notified prior to the
- Provide painted paling fence along any boundary common to lots & municipal reserves as per Council Std. Dwg. S-706. Palings to
- B10. As constructed plans and electronic asset information in D-Spec and R-Spec format must be submitted to Council prior to practical

- 100s agricultural pipe drains (MPA standard drawing EDCM 202) to be placed behind all kerb & channel & buffer pitchers & where directed by the engineer.
- Filling in all properties & road reserves is to be carried out using approved clay fill. Top soil & all vegetable matter to be stripped from site prior to filling. All filling to be carried out in accordance with AS3798-2007 and the geotechnical report. Level 1 ins; and testing to be carried out in accordance with AS3798-2007 Section 8.2. A fill report must be submitted to the Consultant,
- Importing Fill:- All imported fill must be tested by a NATA approved laboratory to ensure it is suitable for use on site, & any contaminates are within accepted levels. Under no circumstances should fill material enter or leave the site without the permission of the supervising engineer & Council works supervisor, prior to it being appropriately tested. All vehicles transporting fill material to & from the site must have appropriate measures in place to ensure that material does not get onto roads & into stomwater
- C4. Batters to be 1 in 5 for fill & 1 in 3 for cut unless noted otherwise


- C5. Cut batters are to be grassed & mulched with a mixture of chopped grass, straw & bitumen emulsion
- C6. Where cut batters exceed 700mm an additional 300mm berm shall be formed behind footpath
- Access ramps are to be constructed where cut batters exceed 1.0m. They are to be graded 1 in 10 for the first 2.5m from the back of path & then at a maximum of 1 in 4 to natural surface.
- The water conduit offset from the lot boundary is given on the water reticulation plan. The contractor must construct conduits to accord with the given offset & ensure that the concreter marks the kerb & footpath exactly above the conduit
- Irrigation conduits are to be DN100 DWV PVC installed beneath the pavement and/or capping layer, if present. Locations are to be
- C10. All footpaths are to be 125mm thick 25MPa concrete with SL72 mesh centrally located in accordance with the MPA standard
- C11. NBN Co to be notified seven (7) days prior to concrete works being placed.
- C12. Electrical distribution pits within footpaths are to be a minimum of 300mm within the edge of the path. Concrete is to be placed
- C14. Traffic control signs, markings & delineators to be installed in accordance with AS1742.2. All line marking is to be long life road marking, with longitudinal lines in thermoplastic & transverse markings in cold applied.
- C15. Driveways to be constructed in accordance with the MPA standard drawings EDCM 501 & EDCM 502. Single driveways to be a
- Kerb transition to take place in the minor street over a 2.0m length from either the tangent point or TP pit
- C17. Existing road works to be reconstructed as required to provide, without discontinuity, a connection in accordance with design
- C18. Provide 2.5m wide shared footpath through reserves as shown on a curvilinear alignment to the satisfaction of the engineer
- C19. Tactile ground surface indicators (TGSI) are to be installed at all pram crossings & pedestrian cross points in accordance with AS1428.4: 2002 & MPA standard drawing EDCM 403.
- C20. If any existing substandard filling is encountered on the site it must be removed and replaced with approved fill material properly compacted to Council requirements. A geo-technical report must be submitted showing details of depth, type of material and density of the fill areas concerned.

- Drainage & pits to be set out from offsets shown rather than from centreline pipe chainages. Centreline of pits at TP's to be offset 1.00m.
- Terra Firma or fibreglass type pit lids are required for all drainage pits & all grates for pits are to be Class D, to comply with AS3996 unless otherwise shown. All drainage works are to be constructed
- All pipes up to and including 750mm in diameter shall be rubber ring jointed (RRJ). Pipes above this size may be flush jointed with external sealing bands. For pipes greater than 900mm and changes in direction between 2 connecting pipes exceeding 10 construct segmented curves using splayed pipes with bandage joints, having deflections within the manufacturer's specification
- Pipe trenches beneath the road pavement, footpath or within 150mm of the kerb & channel to be backfilled with 20mm Class 3 FCR in 150mm layers.
- Property inlets to be constructed as per MPA standard drawing EDCM 701 EDCM 704.
- D7. All proposed drainage stubs to be blanked off at end of pipe with timber planks to the satisfaction of the supervising engineer

PAVEMENT

Modification of the pavement requires approval by the City of Casey works supervisor

DRAWING IND	EX	
DRAWING No.	TITLE	REVISION
1801767-35-001	COVER SHEET	А
1801767-35-002	TYPICAL ROAD CROSS SECTIONS AND GENERAL DETAILS	А
1801767-35-003	RETAINING WALL DETAILS AND PAVEMENT MAKEUP	Α
1801767-35-010	LAYOUT PLAN	А
1801767-35-100	ROAD LONGITUDINAL SECTIONS RATHI STREET AND KENANA STREET	А
1801767-35-101	ROAD LONGITUDINAL SECTIONS CARORA CIRCUIT (SHEET 1 OF 2)	А
1801767-35-102	ROAD LONGITUDINAL SECTIONS CARORA CIRCUIT (SHEET 2 OF 2) & RESERVE FOOTPATH	А
1801767-35-200	ROAD CROSS SECTIONS RATHI STREET & RESERVE FOOTPATH	А
1801767-35-201	ROAD CROSS SECTIONS KENANA STREET	Α
1801767-35-202	ROAD CROSS SECTIONS CARORA CIRCUIT (SHEET 1 OF 2)	Α
1801767-35-203	ROAD CROSS SECTIONS CARORA CIRCUIT (SHEET 2 OF 2)	А
1801767-35-300	INTERSECTION DETAILS (SHEET 1 OF 2)	А
1801767-35-301	INTERSECTION DETAILS (SHEET 2 OF 2)	А
1801767-35-350	SIGNAGE & LINE MARKING PLANS	А
1801767-35-400	DRAINAGE LONGITUDINAL SECTIONS (SHEET 1 OF 2)	А
1801767-35-401	DRAINAGE LONGITUDINAL SECTIONS (SHEET 2 OF 2)	Α
1801767-35-402	PIT SCHEDULE	А



NOT TO SCALE MELWAY REF: 135 F4

Coordinates are on a local plane datum based upon MGA2020 Zone 55 bearings and truncated MGA2020 Zone 55 co-ordinates at PM77. Heights are to AHD vide Permanent Mark PM 56 (Cranbourne) RL 26.7 Bearing Datum is MGA2020 Zone 55 which has been derived by our GPSnet Survey

Plane Grid Coordinates to MGA2020 Zone 55 Grid Coordinates Conversion.

(PLANE SHIFT)

Add + 353,823.586 to Eastings Add +5,780,840.520 to Northings (APPLY SCALE FACTOR) Scale by 0.999846 at point PM77

> ISSUED FOR CONSTRUCTION

	YRIGHT All rights reserved									
	ge Williams & Co. Pty Ltd has granted a licence to the principle to use this docume	nt for its inten								
No unauthorised copying is permitted										
Α	ISSUED FOR CONSTRUCTION	06.06.22	N.T	M.F						
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.	












Project Details		MERIDIAN CENTRAL ESTATE STAGE 35					
		CITY OF CASEY		Scale			
	Drawing	COVER SHEET					
	Title	OOVERGILET		Project Ref	Stage No	Drawing No	Rev
				1801767	35	001	Α





EDCM 202 FOR DETAILS.




CONCRETE SLEEPER **RETAINING WALL DETAILS**

NTS

CONCRETE SLEEPER RETAINING WALL SCHEDULE							
HEIGHT - H(mm)	DEPTH - D(mm)	SOLDIERS SIZE @ 2.4m CTS					
600	900	100 UC 14.8					
800	1200	100 UC 14.8					
1000	1500	100 UC 14.8					

Dmin TO BE GREATER OF THAT SHOWN ABOVE OR 1000mm BELOW ADJACENT SEWER / FRAINAGE



MIX 1 CEMENT: 6 SAND ALL VOIDS FILLED MORTAR JOINTS ON EXPOSED FACE OF WALL TO BE RECESSED TO GIVE A FREESTONE WALL APPEARANCE SELECT COMPACTED BACKFILL 20mm SCREENINGS BACKEILL 300mm WIDTH PLACED AGAINST BACK OF WALL SURROUNDED WITH GEOFABRIC AG DRAIN (TO BE CONNECTED INTO BED BASE COURSE OF YAPEEN SELECT QUARRY ROCK INTO 200mm CONCRETE SLAB 25MPa WITH SL72 MESH. WHEN CONSTRUCTED OVER DRAINAGE PIPES MINIMUM DEPTH TO BE 300mm EXTENDED B MIN 1.00m EACH SIDE OF DRAINAGE PIPE. MASS ROCK RETAINING ALTERNATIVE FOOTING 450 DEEP BEAM OVER SEWER

MASS ROCK RETAINING WALL SCHEDULE										
MAX WALL FOUNDING BASE WIDTH- FRONT FACE CREST DEPTH-D(mm) B(mm) SETBACK-S (mm) WIDTH-C(mm)										
400	400	450	15	300						
500	400	500	15	300						
600	400	500	30	300						
800	400	600	30	300						
1000	400	700	30	300						

WALL DETAIL (TYPE RR)

NTS

RETAINING WALL NOTE R.1

a. WHERE FOOTPATH ABUTS RETAINING WALL CONTINUE CONCRETE UP TO BASE OF

- FOOTING NOTE F.2.
 a. TOE OF WALL SHALL PENETRATE THROUGH ANY FILL MATERIAL & THE NATURAL SILT SOILS TO BE FOUNDED AT LEAST 100mm INTO THIS UNDERLYING NATURAL STILL CLAY OR WEATHERED ROCK.
 ALL EXCAVATIONS SHALL HAVE FOUNDING DEPTHS AND BEARING
- ALL EXCAVATIONS SHALL HAVE FOUNDING DEPTHS AND BEARING
 CAPACITY APPROVED BY THE ENGINEER OR BUILDING SURVEYOR
 BEFORE CONCRETE IS PLACED.
 FOOTING EXCAVATIONS WHICH ARE DEEPEND TO PENETRATE
 THROUGH UNSUITABLE SOILS SHALL BE BACKFILLED UP TO UNDERSIDE OF FOOTINGS
 WITH 15 MPB BLINDING CONCRETE.
 b. ALL EXCAVATION FOUNDING SURFACES SHALL BE LEVEL (NOT INCLINED) CLEAN CUT &
 EDEE OF MILL DO MAGED.
- FREE OF MUD OR WATER. c. ALL SEEPAGE INFLOW SHALL BE REMOVED BEFORE PLACEMENT OF CONCRETE
- . FOOTINGS SHALL BE FOUNDED IN STIFF NATURAL CLAY HAVING A SAFE BEARING

ROCK SIZE NOMINALLY 300 - 900

MASS ROCK RETAINING WALL DETAIL WITH PALING TIMBER FENCE (TYPE RR) OR BOLLARD (BOLLARD BY LANDSCAPE)

NTS

ISSUED FOR CONSTRUCTION

06.06.22 N.T M.F DATE DRN. APP.











;	Project Details	MERIDIAN CENTRAL ESTATE STAGE 35 CITY OF CASEY
	Drawing Title	RETAINING WALL DETAILS


Sheet 03 of 17 AS SHOWN AND PAVEMENT MAKEUP 1801767 35 003 Α



LEGEND

— EXISTING SURFACE
— DESIGN LINE
— FUTURE DESIGN LINE
— EXISTING SURFACE AT
— SOUTH / WEST BOUNDARY
— SOUTH / WEST LIP OF KERB
— EXISTING SURFACE AT
— NORTH / EAST BOUNDARY
— NORTH / EAST LIP OF KERB






© COPYRIGHT All rights reserved Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this docum No unauthorised copying is permitted	nt for its intended purpose				- 04		HORIZONTAL		Designed Date	N. IVETIC 28.04.2022	Bever	ridge Williams	Project Details MERIDIAN CENTRAL ESTATE STAGE 35	Shee	t 05 of	17	
					BROWN PROPERTY GROUP MIER ID I A N	0 5 10	20 30	40 1 4	50 Drawn 5 Approved	N. TABUENA M. FELICIANO	1 Glenferrie Ro	pad	CITY OF CASEY Drawing ROAD LONGITUDINAL SECTIONS	1:500 H	1:50 V	@ A1	
A ISSUED FOR CONSTRUCTION REV DESCRIPTION	06.06.22 N.T M. DATE DRN. A	DESCRIPTION	DATI	E DRN. APP.	CENTRAL		VERTICAL		Date PS Number	29.04.2022 PS902134A	ph: 03 9524 884 www.beveridge	188	RATHI STREET AND KENANA STREET	Project Ref 1801767	Stage No	Drawing No 100	A Rev

K:\Jobs Data\1801767 - Meridian_Eng\Stage 35\Drawings\1801767-35-100-RLS.dv

ISSUED FOR CONSTRUCTION

LEGEND

EXISTING SURFACE
DESIGN LINE
FUTURE DESIGN LINE
EXISTING SURFACE AT
SOUTH / WEST BOUNDARY
SOUTH / WEST LIP OF KERB
EXISTING SURFACE AT
NORTH / EAST BOUNDARY
NORTH / EAST LIP OF KERB




CARORA CIRCUIT - ROAD LONGITUDINAL SECTION

ISSUED FOR CONSTRUCTION


COPYRIGHT All rights reserved Beveridge Williams & Co. Pty Lid has granted a licence to the principle to use this document for its intended purpose. No unauthorised copyring is permitted		HORIZONTAL	Designed N. IVETIC Date 28.04.2022 Beveridge Williams	Project Details MERIDIAN CENTRAL ESTATE STAGE 35	Sheet 06 of 17
	BROWN 👤 🗎		Drawn N. TABUENA	CITY OF CASEY	1:500 H 1:50 V @ A1
	PROPERTY GROUP MERIDIAN		Approved M. FELICIANO 1 Glenferrie Road Malvern VIC 3144	Drawing ROAD LONGITUDINAL SECTIONS	
A ISSUED FOR CONSTRUCTION 06.06.22 N.T M.F	CENTRAL	VERTICAL	Date 29.04.2022 ph: 03.9524.8888 www.beveridgewilliams.com.au	CARORA CIRCUIT	Project Ref Stage No Drawing No Rev 18.017.67 35 1.01 Δ
REV DESCRIPTION DATE DRN. APP. REV DESCRIPTION DATE DRN. APP.			PS Number PS902134A	(SHEET 1 OF 2)	1801767 35 101 A

LEGEND

— EXISTING SURFACE
— DESIGN LINE
— FUTURE DESIGN LINE
EXISTING SURFACE AT
SOUTH BOUNDARY
— SOUTH LIP OF KERB
EXISTING SURFACE AT
NORTH BOUNDARY
— NORTH LIP OF KERB




CARORA CIRCUIT - ROAD LONGITUDINAL SECTION (continued)



RESERVE No.2 FOOTPATH - LONGITUDINAL SECTION

ISSUED FOR
CONSTRUCTION

© COPYRIGHT All rights reserved Beverdige Williams & Co. Ply Ltd has granted a licence to the principle to use this document for its intended pu No unauthorised copying is permitted	pose.				HORIZONTAL		Designed Date	N. IVETIC 28.04.2022	Beveridge Williams	Project Details MERIDIAN CENTRAL ESTATE STAGE 35	Sheet 07 of 17
			BROWN PROPERTY GROUP	0 5 10 0 0.5 1	20 30	40 5 4 5	O Drawn Approved	N. TABUENA M. FELICIANO	1 Glenferrie Road	CITY OF CASEY Drawing ROAD LONGITUDINAL SECTIONS	1:500 H 1:50 V @ A1
A ISSUED FOR CONSTRUCTION 06.06.22 N.T. REV DESCRIPTION DATE DRN		DESCRIPTION DATE DRN. AI	CENTRAL P.	d	VERTICAL		Date PS Number	29.04.2022 PS902134A	ph: 03 9524 8888 www.beveridgewilliams.com.au	CARORA CIRCUIT - (SHEET 2 OF 2) & RESERVE FOOTPATH	Project Ref Stage No Drawing No Rev 1801767 35 102 A



0.050 2.500 0.050 DESIGN LINE ~ DATUM42.0 43.249-43.248-43.218-43.248 DESIGN SURFACE 43.817 43.692 43.454 43.303 EXISTING SURFACE 7.800 8-8-130 -3.200 3.200 6.300 OFFSET CH 233.650 DATUM42.0 43.290 43.289 DESIGN SURFACE 43.883 43.299 EXISTING SURFACE 8.8 9.150 3.800 3.200 6.300 7.800 OFFSET CH 225.517 DATUM42.0 43.409 43.408 DESIGN SURFACE 43.645 EXISTING SURFACE -8:150 -8:150 -6:600 3.800 3.200 6.300 7.800 OFFSET CH 201.647 DATUM42.0 43.534 DESIGN SURFACE 43.439 43.134 43.557 EXISTING SURFACE -8.150 -8.100 -6.600 7.800 OFFSET CH 176.647

ISSUED FOR CONSTRUCTION

© COPPRIONT At rights reserved
Benefidge Williams & Co. Ply Lib has granted a licence to the principle to use this document for its intended purpose.

No unauthorised copying is permitted

A ISSUED FOR CONSTRUCTION

O6.06.22 NT M.F.

REV

DESCRIPTION

DATE DRN. APP. REV

DESCRIPTION


DATE DRN. APP. REV

DESCRIPTION

DATE DRN. APP. REV











Project Details	MERIDIAN CENTRAL ESTATE STAGE 35	Sheet 09 of 17					
	CITY OF CASEY	Scale 1:100 H	1:100 H 1:50 V @ A1				
Drawing Title	ROAD CROSS SECTIONS	Project Ref	Stage No	Drawing No	Rev		
	KENANA STREET	1801767	35	201	A		
	K'Ue	bs Data\1801767 - Meridia	ın_Eng\Stage 35	\Drawings\180176	7-35-200-RXS.dwg		

STRUCTURAL FILL REQUIRED UNDER PAVEMENT AND FOOTPATHS WHERE CONSTRUCTED ABOVE NATURAL SURFACE. REFER GEOTECH REPORT


FOR SPECIFICATION


LEGEND


___ __ _ _ _ EXISTING SURFACE


DESIGN SURFACE


STRUCTURAL FILL















ALIGNMENT NN

Point no	Easting	Northing	RL
NN1	2328.694	673.397	44.780
NN2	2327.971	675.262	44.790
NN3	2316.844	680.171	44.937

 Curve no
 I
 Radius
 Arc
 A
 B
 X
 Y
 L
 Mid point RL

 NN2 - NN3
 90.000
 8.600
 13.509
 2.519
 1.864
 3.291
 2.790
 3.377
 44.836



LIP LINE MM

ALIGNMENT MM

VERTICAL GEOMETRY DATUM RL44 DESIGN LEVEL

EXISTING SURFACE

CHAINAGE


Point no	Easting	Northing	RI
MM1	2314.530	686.138	44.9
MM2	2315.549	686.533	44.9
MM3	2321.327	687.543	44.8
MM4	2327.828	690.284	44.6
MM5	2331.313	692.646	44.5

 Curve no
 I
 Radius
 Arc
 A
 B
 X
 Y
 L
 Mid point RL

 MM2 - MM3
 22,554
 15,000
 5,905
 0,290
 0,217
 1,474
 1,459
 1,476
 44,862

 MM3 - MM4
 48,431
 8,000
 7,289
 0,757
 0,565
 1,804
 1,724
 1,817
 44,739


 MM4 - MM5
 25,878
 9,400
 4,246
 0,239
 0,179
 1,059
 1,046
 1,061
 4,4632



ALIGNMENT PP

 Curve no
 I
 Radius
 Arc
 A
 B
 X
 Y
 L
 Mid point RL

 PP1 - PP2
 90.000
 10.600
 16.650
 3.105
 2.298
 4.056
 3.439
 4.163
 44.643



ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved Beveridge Williams & Co. Ply Ltd has granted a licence to the principle to use this document for its intended purpose. No unauthorised copying is permitted										
Α	ISSUED FOR CONSTRUCTION	06.06.22	N.T	M.F						
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.	












Project Details	MERIDIAN CENTRAL ESTATE STAGE 35 CITY OF CASEY
Drawing Title	INTERSECTION DETAILS


Sheet 12 of 17 N 1:200 @ A1 (SHEET 1 OF 2) 1801767 35 300 Α








NOTES:
ALL STORMWATER DRAINS UP TO AND
INCLUDING 750mm DIA ARE TO BE CLASS 2
R.R.J. PIPES UNLESS NOTED OTHERWISE.





ISSUED FOR CONSTRUCTION


Data\1801767 - Meridian_Eng\Stage 35\Drawings\1801767-35-400-DLS.dwg

Α

Beverid	YRIGHT All rights reserved ge Williams & Co. Pty Ltd has granted a licence to the principle to use this docume uthorised copying is permitted	ent for its inter							
No unau	utnonsed copying is permitted								
A	ISSUED FOR CONSTRUCTION	06.06.22	N.T	M.F					
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.

BROWN PROPERTY GROUP









Project Details	MERIDIAN CENTRAL ESTATE STAGE 35	Sheet 16 of 17					
		Scale					
	CITY OF CASEY	1:500 H 1	@ Λ1 │				
Drawing	DRAINAGE LONGITUDINAL SECTIONS	1.500 11 1	.50 V	ורשש			
Title		Project Ref	Stage No	Drawing No			
	(SHEET 2 OF 2)	1801767	35	401			


						PIT SCI	HEDULE						
		INTE	RNAL	IN	LET	OU	TLET						
PIT NUMBER	TYPE	WIDTH (mm)	LENGTH (mm)	DIAMETER (mm)	INV R.L. (mm)	DIAMETER (mm) INV R.L. (mm)				F.S.L	DEPTH (m)	STANDARD DRAWING	REMARKS
Ex.16	EXISTING PIT			1050	38.304			41.878	3.574		CONNECT DRAIN INTO EXISTING PIT		
17	JUNCTION PIT	1950	900	825	38.763	1050	38.538	41.767	3.229	EDCM 605 & 607	HAUNCH PIT TO 600 x 900 COVER		
				450	39.138								
18	DOUBLE GRATED ENTRY PIT	1050	900	750	39.008	825	38.933	41.293	2.360	EDCM 602 & 607	HAUNCH PIT TO 600 x 900 COVER. INSTALL HEAVY DUTY CLASS D LID		
44	DOUBLE GRATED ENTRY PIT	1050	900	675	39.313	750	39.238	41.419	2.182	EDCM 602 & 607	HAUNCH PIT TO 600 x 900 COVER		
44A	DOUBLE GRATED ENTRY PIT	900	900	675	39.577	675	39.527	41.569	2.042	EDCM 602 & 607	HAUNCH PIT TO 600 x 900 COVER		
E.P1	END PIPE					675	39.85	41.789	1.938		CAP PIPE FOR FUTURE CONNECTION		
59	DOUBLE GRATED ENTRY PIT	750	900	450	39.649	450	39.599	41.428	1.829	EDCM 602 & 607	HAUNCH PIT TO 600 x 900 COVER		
60	DOUBLE GRATED ENTRY PIT	750	900	450	40.159	450	40.109	42.038	1.928	EDCM 602 & 607	HAUNCH PIT TO 600 x 900 COVER		
				300	40.259								
				300	40.259								
61	GRATED ENTRY PIT	750	900	450	40.627	450	40.577	42.612	2.035	EDCM 601 & 607	HAUNCH PIT TO 600 x 900 COVER		
62	GRATED ENTRY PIT	600	900	450	40.910	450	40.860	43.106	2.246	EDCM 601			
63	GRATED ENTRY PIT	600	900	375	41.155	450	41.08	43.102	2.022	EDCM 601			
				375	41.155								
64	TANGENT POINT			375	41.299	375	41.299	43.193	1.895				
E.P3	END PIPE					375	41.592	43.391	1.799		CAP PIPE FOR FUTURE CONNECTION		
68	JUNCTION PIT	600	900	300	40.545	300	40.495	42.177	1.682	EDCM 605			
69	JUNCTION PIT	600	900	300	41.323	300	41.273	42.249	0.976	EDCM 605			
E.P2	END PIPE					300	41.579	42.493	0.915		CAP PIPE FOR FUTURE CONNECTION		
73	GRATED ENTRY PIT	600	900	375	41.574	375	41.524	43.293	1.769	EDCM 601			
				300	41.599								
74	JUNCTION PIT	600	900	300	42.190	375	42.115	44.022	1.907	EDCM 605			
				300	42.190								
75	GRATED ENTRY PIT	600	900	300	42.806	300	42.756	44.569	1.813	EDCM 601			
76	GRATED ENTRY PIT	600	900	300	43.000	300	42.950	44.908	1.959	EDCM 601			
				300	43.000								
77	JUNCTION PIT	600	900	300	43.153	300	43.103	44.962	1.859	EDCM 605			
78	JUNCTION PIT	600	900	300	43.340	300	43.290	45.035	1.745	EDCM 605			
79	GRATED ENTRY PIT	600	900	300	43.688	300	43.638	45.184	1.546	EDCM 601			
80	GRATED ENTRY PIT	600	900			300	43.769	45.169	1.400	EDCM 601			
81	JUNCTION PIT	600	900	300	42.536	300	42.486	44.58	2.094	EDCM 605			
82	JUNCTION PIT	600	900	225	43.158	300	43.083	44.847	1.764	EDCM 605			
E.P4	END PIPE			-		225	43.282	44.927	1.645		CAP PIPE FOR FUTURE CONNECTION		
107	GRATED ENTRY PIT	600	900	300	43.211	300	43.161	44.912	1.751	EDCM 601			
108	GRATED ENTRY PIT	600	900	300	43.438	300	43.388	45.080	1.692	EDCM 601			
109	GRATED ENTRY PIT	600	900			300	43.653	45.053	1.400	EDCM 601			
110	GRATED ENTRY PIT	600	900			300	41.890	43.290	1.400	EDCM 601			
122	DOUBLE GRATED ENTRY PIT	600	900			300	40.724	42.139	1.416	EDCM 602			

ISSUED FOR CONSTRUCTION

	PYRIGHT All rights reserved							Г		
Beveri	dge Williams & Co. Pty Ltd has granted a licence to the principle to use this docume									
NO Ulia	No unauthorised copying is permitted									
										ı
										ı
										ı
A	ISSUED FOR CONSTRUCTION	06.06.22	N.T	M.F						1
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.	







Designed Date	N. IVETIC 28.04.2022
Drawn	N. TABUENA
Approved Date	M. FELICIANO 29.04.2022

Beveridge Williams

1 Glenferrie Road
Malvern VIC 3144
ph: 03 9524 8888

Project Details	MERIDIAN CENTRAL ESTATE	Sheet 17 of 17					
	CITY OF CASEY		1.500 H 1.50 V @ A1				
Drawing	DIT SCHEDI II E		1.50011	1.50 V	@ /\ i		
Title	TH SOILDOLL		Project Ref	Stage No	Drawing No	Rev	
			1801767	35	402	Α	
	Details Drawing	Details STAGE 35 CITY OF CASEY	Details STAGE 35 CITY OF CASEY Detailing PIT SCHEDULE	STAGE 35 CITY OF CASEY PIT SCHEDULE MICHIDIAN CENTRAL ESTATE Sneet Scale 1:500 H	Details STAGE 35 CITY OF CASEY Drawling PIT SCHEDULE Sneet 17 OF	Desking Tide PIT SCHEDULE Sneet 17 of 17 Scale 1:500 H 1:50 V @ A1 Project Ref Stage No Drawing No	

K:\Jobs Data\1801767 - Meridian_Eng\Stage 35\Drawings\1801767-35-400-DLS.dwg