

REPORT

Level 1 Geotechnical Testing and Inspection Authority Services

Meridian Central Estate Stage 42 Clyde North Lots 4201 to 4234

Prepared for:

Greenridge Properties Pty Ltd.

16 May 2023

Our Ref: 3807351.042.v1

Table of contents

1	Intro	oduction	3
2	Proj	ect details	3
	2.2	Roles	4
	2.3	Dates on Site	4
	2.4	Included Areas	4
	2.5	Excluded Areas	5
	2.6	Specification	5
3	Insp	5	
	3.1	Earthworks	5
	3.2	Fill Material	6
	3.3	Subgrade Assessment / Proof Roll	7
	3.4	Engineered Fill Construction	8
	3.5	Density testing	10
4	Cond	clusion	11
5	qqA	licability	12

Appendix A : Location Plan

Appendix B : Hilf Density Test Summary

Appendix C : NATA Endorsed Laboratory Reports

Appendix D : Controlled Fill Certificate

Date: 16 May 2023 Job No: 3807351.042

Document Control

Title: Leve	Title: Level One Inspection and testing Services.											
Date	Version	Description	Prepared by:	Reviewed by:	Authorised by							
16 May 2023	1	3807351.042.V1 Level One Report Stage 42	STPA and RHB	RWMC	TJJC							

1 Introduction

Chadwick Geotechnics Pty Ltd (Chadwick Geotechnics), was engaged by Greenridge Properties Pty Ltd (Greenridge), to provide Level 1 Geotechnical Inspection and Testing Authority (GITA) services for the earthworks conducted within Stage 42 of the Meridian Central Estate in Clyde North, between 7 September 2022 and 16 March 2023.


Level 1 GITA services as defined in AS3798-2007 "Guidelines on Earthworks for Commercial and Residential Development," requires full time inspection and field and laboratory testing of earthworks in accordance with AS1289 "Methods of Testing Soils for Engineering Purposes."

2 Project details

The Stage 42 site is located North of Hardys Road, Clyde North. The site is to the East of Stage 41, and West of Stage 43.

The included works are shown on the Site Plan in **Appendices A**. Figure 2.1 below is an extract from Nearmap taken at the time of writing this report.

Figure 2: extract from Nearmap



2.2 Roles

The organisations and their roles are presented in Table 2.1 below

Table 2: Roles on the Project

Role	Organisation
Developer	Greenridge Properties Pty Ltd
Geotechnical Inspection and Testing Authority (GITA)	Chadwick Geotechnics Pty Ltd
Designer / Superintendent	Beveridge Williams Pty Ltd
Earthworks Contractor	Brown Property Group Pty Ltd

Chadwick Geotechnics undertook the field density testing, and the compaction control laboratory testing was conducted in our NATA accredited laboratories.

2.3 Dates on Site

Geotechnical technicians and engineering staff from Chadwick Geotechnics were onsite for the duration of the earthworks program on the days shown in Table 2.2 below.

Table 2.2: Level 1 GITA – onsite presence

Month	Dates on site
September 2022	7, 8, 12, 27, 28, 29, 30
October 2022	1, 3, 4, 5, 19, 21, 24
November 2022	8, 11, 12, 16, 18, 23, 26, 29, 30
December 2022	1, 2, 5, 7, 8, 19, 20, 21
January 2023	3, 4, 5, 6, 7, 9, 10, 13
February 2023	24, 27
March 2023	1, 2, 3, 4, 7, 16

2.4 Included Areas

This report is applicable to material placed by the contractor on the residential lots within Stage 42, as shown on the Site Plan in **Appendix A**, and with reference to Section 2.6 (Excluded Areas) of this report.

The following Lots were filled (or partially filled) during the Level 1 GITA supervision:

Lot 4201 to 4234

2.5 Excluded Areas

This report does not include fill outside the general boundary of the filled areas as shown in **Appendix A** of this report.

Backfill of trenches for the underground services, fill on footpaths, driveways and roads, or placement of topsoil, were not part of the scope for the works supervised by Chadwick Geotechnics.

2.6 Specification

Project specifications were prepared by Beveridge Williams Pty Ltd for the project. The works were to be conducted in general accordance with the 'Guidelines on earthworks for commercial and residential developments' of AS 3798-2007.

The following items were adopted as part of the project earthworks specifications:

- All Filling, in excess, of 200mm depth within the residential lots shall be undertaken to specifications satisfying the requirements of AS 3798-2007 "Guidelines on Earthworks for Commercial and Residential Development".
- The fill soils to comply with the 'Suitable Material' in accordance with Section 4.4 of the AS3798-2007, and the following:
 - o Maximum particle size of 150mm.
 - o Particles over 37.5mm diameter not to exceed 20% of the material.
 - Organic soils, topsoil, silts, or soils containing organic matter, wood, plastics, metal, or other deleterious materials are not acceptable.
- Subgrade to be proof rolled prior to placement of an engineered fill.
- Fill to be compacted in near horizontal layers not exceeding 250mm loose thickness.
- Compaction to achieve a ratio of at least 95% Standard Maximum Dry Density (SMDD).
- Frequency of testing to be in accordance with Table 8.1 of AS3798-2007.
- Finished fill surface to be surveyed prior to placement of topsoil.

3 Inspection and Testing

The inspection and testing of earthworks have been carried out in accordance with AS3798-2007, 'Guidelines on earthworks for commercial and residential developments', with a frequency of field density tests as per Table 8.1 (explained in Section 4.5 of this report). Compaction control laboratory testing was performed in a Chadwick Geotechnics' NATA accredited laboratory in accordance with AS1289 'Methods of Testing Soils for Engineering Purposes'.

3.1 Earthworks

The earthworks for the project comprised of the following phases:

- Stripping of topsoil from the proposed fill areas.
- Assessment, remediation, and proof rolling of subgrade.
- Geotechnical compliance testing of the soils used for fill, and,
- Placement and compaction of engineered fill.

Job No: 3807351.042

3.2 Fill Material

Material used for the construction of the fill comprised of local gravelly and silty clays won from the road boxing and trench excavations on this and the surrounding sites.

Five samples were taken from the site comprising local material used for fill was taken for geotechnical compliance testing during the works. The material compliance test results are summarised in Table 3.1 The laboratory test certificates are attached in **Appendix C.**

Table 3.1: Compliance test result summary

Sample #	Particle	Size Dist	ribution	(PSD)		Liquid	Plastic	Plasticity		
	37.5	13.2	4.75	1.18	425	0.75	Limit %	Limit %	Index %	
	mm	mm	mm	mm	μm	μm				
S22DS-08310	100	99	95	90	84	63	54	22	32	
S22DS-08769	100	100	94	88	79	43	38	13	25	
S22DS-09640	100	99	96	91	87	71	72	20	52	
S23DS-00028	100	100	93	88	79	42	30	12	18	
S23DS-00115	100	96	87	79	72	43	35	15	20	

The laboratory test results indicated material is sandy clay of medium to high plasticity.


The material was deemed as being derived from natural soils. The soil is considered as 'Suitable Material' in accordance with Section 4.4 of the AS3798-2007.

The fill material was not tested for classification of 'Fill Material' as defined in EPA Publication IWRG621. Environmental testing is not within the Chadwick Geotechnics scope.

Any observed organic or deleterious matter including any oversize cobbles or boulders were removed from the tested areas during the fill placement.

Below are photographs of typical materials used during construction.

Figure 3.1: Photographs of the material used on site



3.3 Subgrade Assessment / Proof Roll


The Subgrade of the site was progressively assessed during the period Chadwick Geotechnics personnel were on site.

Subgrade assessments were conducted following the removal of the topsoil and natural soils that were present on site.

The subgrade inspections were performed in accordance with the Level 1 guidelines presented in AS 3798–2007 Section 5.5. No soft spots or deflections were encountered during the inspections and the area was found to be firm and free of vegetation and other deleterious material.

Below are photographs of the subgrade assessment phase at the project.

Figure 3.2: Subgrade assessment photographs



3.4 Engineered Fill Construction

All fill material was brought by dump trucks from the local stockpiles, spread with a bulldozer and compacted with a pad foot roller. A water cart was present onsite during the works for moisture conditioning of the materials.

All fill material was placed in lift sequences comprising horizontal layers. Chadwick Geotechnics verified that the surface of the stripped area, and that of additional lifts, was thoroughly scarified and moisture conditioned prior to placement of additional layers to prevent delamination at the layer interface. Once the placed fill was approved, the layer was compacted accordingly.

Chadwick Geotechnics personnel were on site on a fulltime basis during the placement, moisture conditioning, compaction, and testing of the fill on the dates noted in Table 2.2 of this report.


The following machinery was on site during earthworks.

Table 3.2: Earthworks plant On-site

Equipment type	Model
Dozer	Caterpillar D6 Dozer
Pad foot roller	Caterpillar compactor B15K Pad-Foot Roller
Water cart	Off-Road Water Cart with spray bars
Dump Trucks	Volvo Dump Trucks and Road Trucks
Excavator	Caterpillar
Scraper	

Below are photographs of typical machinery on site during construction.

Figure 3.3: General Earthwork machinery and fill construction photographs



Job No: 3807351.042

3.5 Density testing

Field density and moisture content testing was undertaken progressively during construction on the compacted fill using a calibrated portable density and moisture gauge in accordance with AS 1289.5.8.1. The HILF rapid compaction test was used for peak converted wet density determinations in accordance with AS 1289.5.7.1. Test locations were recorded using a handheld GPS unit. A site plan showing the field density test locations is provided in **Appendix A**.

Testing was undertaken under the frequencies listed below, subject to the area and volume worked on the day of testing:

- 1 test per material type per layer per 2500m² or 1 test per 500m³ distributed reasonably evenly or 3 tests per lot whichever requires the most tests in accordance with Type 1 Earthworks (large scale operations) as defined in Table 8.1 of the AS 3798-2007;
- Fill to be compacted in near horizontal layers.
- Compaction to achieve a ratio of at least 95% Standard MDD (maximum dry density).

One hundred and seven (107) tests were performed during the filling process across the works area. Thirteen (13) of the tests did not achieve the required density and or moisture ratio initially. The failed area was reworked and retested accordingly. The retests returned passing density and moisture test results.

A summary table of HILF density tests is provided in **Appendix B** and the laboratory test reports are provided in **Appendix C**.

Job No: 3807351.042

4 Conclusion

On the basis, of our inspections and after considering all test results relating to the project, it is our opinion, so far as it is to be determined, that:

- The materials, used by the earth-works contractor met the geotechnical property requirements of the specification.
- The sourced fill was, considered to be natural, clean, and suitable for use at the site.
- The fill material placed was tested at a suitable frequency in accordance with AS 3798-2007-Table 8.1 and the results indicate the compacted clay achieved the density requirement of the specification.
- Given the consistent construction practices followed by the earthworks contractor and as
 witnessed by the Chadwick Geotechnics, combined with the satisfactory verification of test
 results achieved, it is inferred that areas of the site between test locations were performed to
 the same standard as those areas that have been tested.
- Based on observations made by Chadwick Geotechnics Level 1 personal and the results of field and laboratory tests, we consider that the engineered fill within the site (noted in Section 2.5), as far as we have been able to reasonably determine, have been placed in general accordance with the intent of the specification.
- It is our opinion that the earthworks undertaken have been performed in accordance with the requirements of Section 8.2 Level 1 Inspection and Testing AS3798-2007 Guidelines on Earthworks for Commercial and Residential Developments.

After our last day on site the Contractor is responsible to maintain the engineered fill in satisfactory condition. Should the fill be not maintained or protected with a sacrificial layer of topsoil or other fill, the uppermost layers of the engineered fill may deteriorate from the weather causing shrink/swell cracking and may need to be remediated prior to further construction on the site. Chadwick Geotechnics have not provided supervision since this date and are not responsible for any deterioration that may have occurred.

Job No: 3807351.042

5 Applicability

Chadwick Geotechnics Pty Ltd

PE0005222

This report has been prepared for the exclusive use of our client in good faith and in accordance with the Chadwick Geotechnics quality system for the earthworks filling at the site.

This report is based on the nature of the project and the prevailing conditions between 7 September 2022 and 16 March 2023. No responsibility or liability will be accepted, and Chadwick Geotechnics is indemnified to the full extent permitted by law in respect of the use of this report where there has been a change in the nature of the project or the conditions on site that may alter or affect the conclusions of this report.

Should you require any further information regarding this report, please do not hesitate to contact the undersigned on (03) 8796 7900.

Report prepared by:

Authorised for Chadwick Geotechnics Pty Ltd by:

Lober Barden

Timothy Chadwick

Project Manager


Report reviewed by:

Report reviewed by:

Robert McKenzie

Senior Associate Geotechnical Engineer

Appendix A: Location Plan





PROJECT No.	3807351.0	142	
DESIGNED	STPA	May.23 May.23	
DRAWN CHECKED	KMJA	May.23	
ADDDOVED	_	ATE	

TITLE 1.FVEL CNIE HILF DENSITY TESTING

H. L. C.E. (CI.) TEJ I LOCA (C. V. C. A. V.)

SCALE (A3) 1:1000 FIG No. 3807351.042-F01 REV 1

Appendix B: Hilf Density Test Summary



Chadwick Geotechnics 25 Metcalf Street Dandenong South VIC 3175 Tel: (03) 8796 7900



HILF Density Testing - Field Summary

Report No	Sample No	Date	Lot No	Easting	Northing	Layer/RL	Density Ratio	Moisture Variation	Pass / Fail	Comments (Retest No) Compliance test taken ect
HDR:W22DS01787	S22DS-07016	7/09/2022	4228	356350	5781052	1	96.5	2 wet	Pass	
HDR:W22DS01787	S22DS-07017	7/09/2022	4226	356319	5781064	1	96	1.5 wet	Pass	
HDR:W22DS01794	S22DS-07048	8/09/2022	4224	356274	5781052	1	97.5	1.5 wet	Pass	
HDR:W22DS01807	S22DS-07085	12/09/2022	4230	356381	5781044	1	99.5	2 wet	Pass	
HDR:W22DS01914	S22DS-07627	27/09/2022	4225	356367	5781057	40.95	93	1.5 wet	Fail	See Retest 07794 & 07831
HDR:W22DS01926	S22DS-07673	28/09/2022	4225	356286	5781069	FSL	95	0.5 dry	Pass	
HDR:W22DS01937	S22DS-07714	29/09/2022	4230	356378	5781039	2	95.5	ОМС	Pass	
HDR:W22DS01937	S22DS-07715	29/09/2022	4228	356351	5781043	2	95	ОМС	Pass	
HDR:W22DS01937	S22DS-07716	29/09/2022	4227	356318	5781044	2	96	ОМС	Pass	
HDR:W22DS01961	S22DS-07794	30/09/2022	4225	356367	5781057	2	96.5	ОМС	Pass	Retest of S22DS-07627
HDR:W22DS01961	S22DS-07795	30/09/2022	4225	356368	5781050	3	99	ОМС	Pass	
HDR:W22DS01961	S22DS-07796	30/09/2022	4226	356310	5781041	3	98	ОМС	Pass	
HDR:W22DS01962	S22DS-07797	1/10/2022	4228	356354	5781066		100.5	0.5 dry	Pass	
HDR:W22DS01974	S22DS-07831	3/10/2022	4229	356367	5781057	2	100	ОМС	Pass	Retest of S22DS-07627
HDR:W22DS01974	S22DS-07832	3/10/2022	4230	356375	5781042	3	96.5	0.5 dry	Pass	
HDR:W22DS01991	S22DS-07904	4/10/2022	4226	356320	5781065	4	96.5	ОМС	Pass	
HDR:W22DS02001	S22DS-07934	5/10/2022	4229	356367	5781054	4	100	OMC	Pass	
HDR:W22DS02085	S22DS-08284	19/10/2022	4232	356414	5781045		102.5	1 dry	Pass	
HDR:W22DS02085	S22DS-08285	19/10/2022	4233	356422	5781084		97.5	ОМС	Pass	



Chadwick Geotechnics 25 Metcalf Street Dandenong South VIC 3175 Tel: (03) 8796 7900



HILF Density Testing - Field Summary

Report No	Sample No	Date	Lot No	Easting	Northing	Layer/RL	Density Ratio	Moisture Variation	Pass / Fail	Comments (Retest No) Compliance test taken ect
HDR:W22DS02111	S22DS-08379	21/10/2022	4232	356405	5781030		98	ОМС	Pass	
HDR:W22DS02111	S22DS-08380	21/10/2022	4233	356416	5781077		94.5	ОМС	Fail	See Retest 08581
HDR:W22DS02144	S22DS-08579	24/10/2022	4231	356397	5781038	3	97	0.5 dry	Pass	
HDR:W22DS02144	S22DS-08580	24/10/2022	4233	356415	5781068	3	98.5	0.5 dry	Pass	
HDR:W22DS02144	S22DS-08581	24/10/2022	4233	356417	5781083		99	ОМС	Pass	Retest of S22DS-08380
HDR:W22DS02198	S22DS-08770	8/11/2022	4232	356411	5781043	40.32	97	2.5 wet	Pass	
HDR:W22DS02198	S22DS-08771	8/11/2022	4234	356397	5781084	41.16	98	ОМС	Pass	
HDR:W22DS02220	S22DS-08881	11/11/2022	4202	356409	5781136	41.07	104	1.5 dry	Pass	
HDR:W22DS02220	S22DS-08882	11/11/2022	4204	356415	5781173	41.74	99.5	2.5 dry	Pass	
HDR:W22DS02220	S22DS-08883	11/11/2022		356423	5781195	42.7	100	0.5 dry	Pass	
HDR:W22DS02218	S22DS-08876	12/11/2022	4233	356416	5781079	43.25	101	0.5 dry	Pass	
HDR:W22DS02254	S22DS-09011	16/11/2022	4205	356431	5781173	42.54	97.5	ОМС	Pass	
HDR:W22DS02254	S22DS-09012	16/11/2022	4203	356425	5781149	425.05	100	ОМС	Pass	
HDR:W22DS02254	S22DS-09013	16/11/2022	4201	356420	5781112	41.44	96.5	ОМС	Pass	
HDR:W22DS02275	S22DS-09110	18/11/2022	4207	356425	5781199	43.57	99	0.5 dry	Pass	
HDR:W22DS02275	S22DS-09111	18/11/2022	4206	356420	5781183	43.37	98.5	ОМС	Pass	
HDR:W22DS02275	S22DS-09112	18/11/2022	4204	356412	5781164	42.98	100.5	ОМС	Pass	
HDR:W22DS02275	S22DS-09113	18/11/2022	4202	356409	5781138	42.27	98.5	ОМС	Pass	



Chadwick Geotechnics 25 Metcalf Street Dandenong South VIC 3175 Tel: (03) 8796 7900



HILF Density Testing - Field Summary

Report No	Sample No	Date	Lot No	Easting	Northing	Layer/RL	Density Ratio	Moisture Variation	Pass / Fail	Comments (Retest No) Compliance test taken ect
HDR:W22DS02310	S22DS-09334	23/11/2022	4205	356416	5781178	43.13	103	1 dry	Pass	
HDR:W22DS02310	S22DS-09335	23/11/2022	4203	356413	5781153	42.8	102	1 dry	Pass	
HDR:W22DS02310	S22DS-09336	23/11/2022	4201	356415	5781116	41.3	102.5	2 dry	Pass	
HDR:W22DS02334	S22DS-09409	26/11/2022	4124	356387	5781139	42.68	107.5	3 dry	Fail	See Retest 9530
HDR:W22DS02334	S22DS-09410	26/11/2022	4125	356376	5781131	42.43	107.5	3 dry	Fail	See Retest 9529
HDR:W22DS02334	S22DS-09411	26/11/2022	4127	356400	5781125	42.24	101	1 dry	Pass	
HDR:W22DS02336	S22DS-09412	26/11/2022	4201	356418	5781112	41.42	97	0.5 dry	Pass	
HDR:W22DS02336	S22DS-09413	26/11/2022	4214	356477	5781139	41.17	94	ОМС	Fail	See Retest S22DS-09601
HDR:W22DS02336	S22DS-09414	26/11/2022	4216	356466	5781112	40.63	96.5	ОМС	Pass	
HDR:W22DS02363	S22DS-09529	29/11/2022	4214	356465	5781135	42.43	99.5	2.5 dry	Pass	Retest of S22DS-09410
HDR:W22DS02363	S22DS-09530	29/11/2022	4201	356417	5781118	42.68	97	ОМС	Pass	Retest of S22DS-09409
HDR:W22DS02375	S22DS-09583	30/11/2022	4213	356454	5781156	42.16	106	2 dry	Fail	See Retest 9646
HDR:W22DS02381	S22DS-09601	1/12/2022	4215	356458	5781131	41.36	104.5	2.5 dry	Pass	Retest of S22DS-09413
HDR:W22DS02398	S22DS-09646	2/12/2022	4213	356454	5781156		107.5	2.5 dry	Fail	Retest of 09583, See Retest 9729
HDR:W22DS02406	S22DS-09666	5/12/2022	4214	356459	5781142	41.82	107	5 dry	Fail	See Retest 9730
HDR:W22DS02406	S22DS-09667	5/12/2022	4216	356458	5781117	40.939	106.5	3 dry	Pass	
HDR:W22DS02406	S22DS-09668	5/12/2022	4212	356457	5781174	42.541	105	3 dry	Pass	
HDR:W22DS02422	S22DS-09729	7/12/2022	4213 / 4	356462	5781162	42.25	103.5	2.5 dry	Pass	Retest of S22DS-09646



Chadwick Geotechnics 25 Metcalf Street Dandenong South VIC 3175 Tel: (03) 8796 7900



HILF Density Testing - Field Summary

Report No	Sample No	Date	Lot No	Easting	Northing	Layer/RL	Density Ratio	Moisture Variation	Pass / Fail	Comments (Retest No) Compliance test taken ect
HDR:W22DS02422	S22DS-09730	7/12/2022	4214 / 3	356459	5781142	-	98	ОМС	Pass	Retest of S22DS-09666
HDR:W22DS02422	S22DS-09731	7/12/2022	4215 / 4	356461	5781129	41.63	97	0.5 dry	Pass	
HDR:W22DS02436	S22DS-09822	8/12/2022	4214 / 5	356476	5781143	41.687	98	0.5 dry	Pass	
HDR:W22DS02436	S22DS-09823	8/12/2022	4212 / 5	356480	5781175	42.092	95	0.5 dry	Pass	
HDR:W22DS02436	S22DS-09824	8/12/2022	4216 / 5	356464	5781118	41.379	97.5	0.5 dry	Pass	
HDR:W22DS02514	S22DS-10052	19/12/2022	4213 / 6	356469	5781156	42.27	98	0.5 dry	Pass	
HDR:W22DS02514	S22DS-10053	19/12/2022	4215 / 6	356458	5781130	41.84	102.5	0.5 dry	Pass	
HDR:W22DS02514	S22DS-10054	19/12/2022	4216 / 7	356457	5781119	41.69	102	1 dry	Pass	
HDR:W22DS02514	S22DS-10055	19/12/2022	4214 / 7	356462	5781145	42.12	102	2.5 dry	Pass	
HDR:W22DS02514	S22DS-10056	19/12/2022	4212 / 7	356464	5781177	42.81	106.5	4.5 dry	Fail	See Retest areas S22DS-10268 & S23DS-00003
HDR:W22DS02539	S22DS-10186	20/12/2022	4217 / 1	356453	5781103	40.61	96	OMC	Pass	
HDR:W22DS02539	S22DS-10187	20/12/2022	4219 / 1	356452	5781073	39.97	97.5	ОМС	Pass	
HDR:W22DS02556	S22DS-10268	21/12/2022	4212/7	356464	5781177	42.81	102	2.0 dry	Pass	Retest of area S22DS-10056
HDR:W22DS02556	S22DS-10269	21/12/2022	4212/8	356466	5781172	42.86	100.5	1.0 dry	Pass	
HDR:W22DS02556	S22DS-10270	21/12/2022	4218/2	356449	5781087	40.52	95	ОМС	Pass	
HDR:W22DS02556	S22DS-10271	21/12/2022	4220/2	356443	5781057	39.88	95	ОМС	Pass	
HDR:W23DS00001	S23DS-00001	3/01/2023	4217	356450	5781102	41.01	96	2.0 Dry	Pass	
HDR:W23DS00001	S23DS-00002	3/01/2023	4219	356448	5781070	40.34	95.5	OMC	Pass	



Chadwick Geotechnics 25 Metcalf Street Dandenong South VIC 3175 Tel: (03) 8796 7900



HILF Density Testing - Field Summary

Report No	Sample No	Date	Lot No	Easting	Northing	Layer/RL	Density Ratio	Moisture Variation	Pass / Fail	Comments (Retest No) Compliance test taken ect
HDR:W23DS00001	S23DS-00003	3/01/2023	4212	356469	5781185	-	94.5	0.5 Dry	Fail	Retest of area S22DS-10056, See Retest S23DS-00007
HDR:W23DS00004	S23DS-00006	4/01/2023	4201	356425	5781118	41.68	95.5	OMC	Pass	
HDR:W23DS00004	S23DS-00007	4/01/2023	4212	356465	5781187	42.8	95.5	ОМС	Pass	Retest S23DS-00003
HDR:W23DS00004	S23DS-00008	4/01/2023	4218	356462	5781078	40.64	98.5	0.5 dry	Pass	
HDR:W23DS00004	S23DS-00009	4/01/2023	4216	356462	5781115	41.37	99	ОМС	Pass	
HDR:W23DS00009	S23DS-00025	5/01/2023	4220	356451	5781055	40.06	99.5	ОМС	Pass	
HDR:W23DS00009	S23DS-00026	5/01/2023	4217	356467	5781098	41.08	101	0.5 Wet	Pass	
HDR:W23DS00009	S23DS-00027	5/01/2023	4219	356455	5781073	40.49	101.5	0.5 Wet	Pass	
HDR:W23DS00011	S23DS-00029	6/01/2022	4207	356425	5781204	43.56	101	0.5 wet	Pass	
HDR:W23DS00011	S23DS-00030	6/01/2022	4211	356461	5781190	42.36	101	0.5 dry	Pass	
HDR:W23DS00011	S23DS-00031	6/01/2022	4208	356436	5781215	43.6	97	0.5 dry	Pass	
HDR:W23DS00011	S23DS-00032	6/01/2022	4211	356462	5781194	42.73	98.5	0.5 dry	Pass	
HDR:W23DS00015	S23DS-00043	7/01/2023	4211 / 3	356465	5781194	42.7	103.5	2.0 dry	Pass	
HDR:W23DS00015	S23DS-00044	7/01/2023	4210 / 3	356479	5781195	42.13	102.5	2.0 dry	Pass	
HDR:W23DS00024	S23DS-00075	9/01/2023	4208 / 4	356416	5781223	43.99	101	2.0 dry	Pass	
HDR:W23DS00024	S23DS-00076	9/01/2023	4210 / 4	356461	5781206	42.9	100	0.5 dry	Pass	
HDR:W23DS00024	S23DS-00077	9/01/2023	4211 / 5	356461	5781192	43.16	99	2.5 dry	Pass	



Chadwick Geotechnics 25 Metcalf Street Dandenong South VIC 3175 Tel: (03) 8796 7900



HILF Density Testing - Field Summary

Report No	Sample No	Date	Lot No	Easting	Northing	Layer/RL	Density Ratio	Moisture Variation	Pass / Fail	Comments (Retest No) Compliance test taken ect
HDR:W23DS00034	S23DS-00113	10/01/2023	4210 / 5	356471	5781206	42.96	103.5	1.5 dry	Pass	
HDR:W23DS00034	S23DS-00114	10/01/2023	4211 / 6	356475	5781188	43.12	104	2.0 dry	Pass	
HDR:W23DS00083	S23DS-00261	13/01/2023	4222	356446	5781039	39.42	101.5	2.5 dry	Pass	
HDR:W23DS00171	S23DS-00550	24/01/2023	4209 / -	356426	5781236	44.209	99.5	0.5 dry	Pass	
HDR:W23DS00514	S23DS-01694	24/02/2023	4217 / 7	356470	5781102	41.22	97.5	0.5 dry	Pass	
HDR:W23DS00514	S23DS-01695	24/02/2023	4215 / 8	356473	5781128	41.769	99.5	0.5 wet	Pass	
HDR:W23DS00514	S23DS-01696	24/02/2023		356475	5781157	42.609	104.0	2.0 dry	Pass	
HDR:W23DS00514	S23DS-01697	24/02/2023	4210 / 7	356476	5781208	-	94.5	2.5 dry	Fail	See Retest S23DS-01757
HDR:W23DS00537	S23DS-01757	27/02/2023	4210 / 7	356476	5781208	43.103	99.5	4.0 dry	Fail	Retest of S23DS-01697, See Retest 1863
HDR:W23DS00579	S23DS-01863	1/03/2023		356476	5781208		95	ОМС	Pass	Retest of S23DS-01757
HDR:W23DS00604	S23DS-01959	2/03/2023	4219 / 7	356468	5781065	40.439	98.0	ОМС	Pass	
HDR:W23DS00617	S23DS-01988	3/03/2023	4220 / 8	356461	5781051	40.15	101.0	OMC	Pass	
HDR:W23DS00619	S23DS-01989	4/03/2023	4211 / 8	356478	5781193	43.178	99.5	4.0 dry	Fail	See Retest S23DS-02103
HDR:W23DS00619	S23DS-01990	4/03/2023	4210 / 9	356467	5781221	43.367	97.0	ОМС	Pass	
HDR:W23DS00650	S23DS-02103	7/03/2023	4211 / 8	356478	5781193	43.178	102	2.5 dry	Pass	Retest of S23DS-01989
HDR:W23DS00742	S23DS-02361	16/03/2023	4221 / 4	356434	5781040	39.917	99.0	2.5 dry	Pass	
HDR:W23DS00742	S23DS-02362	16/03/2023	4223 / 4	356459	5781037	39.475	102.5	2.0 dry	Pass	

Appendix C: NATA Endorsed Laboratory Reports





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01787

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA **NATA**

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 15/09/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (1% Dry to 3% Wet of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Silty Clay with traces of Gravel

Sample Data				
Sample ID	S22DS-07016	S22DS-07017		
Field Sample ID	1	2		
Client Sample ID	1	2		
Date Tested	7/09/2022	7/09/2022		
Time Tested	16:00	15:50		
E:	2493.355 (356350)	2527.339 (356319)		
N:	218.252 (5781052)	206.797 (5781064)		
EL:	42.064	41.495		
Lot / Layer:	4228 / 1	4226 / 1		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	18.0	17.9		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.02	1.99		
Field Dry Density (t/m³)	1.71	1.69		
Peak Converted Wet Density (t/m³)	2.09	2.07		
Optimum Moisture Content (%)	16.0	16.0		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	111.5	110.5		
Moisture Variation (%)	2.0 wet	1.5 wet		
Hilf Density Ratio (%)	96.5	96.0		

Comments





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01794

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

IATA

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 15/09/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (1% Dry to 3% Wet of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Silty Clay with Traces of Gravel

Sample Data								
Sample ID	S22DS-07048							
Field Sample ID	1							
Client Sample ID	3							
Date Tested	8/09/2022							
Time Tested	13:50							
E:	2451.895 (356274)							
N:	211.778 (5781052)							
EL:	41.916							
Lot / Layer:	4224 / 1							
Field and Laboratory Data								
Depth of Test (mm)	175							
Depth of Layer (mm)	200							
AS Sieve Size (mm)	19.0							
Oversize Wet (%)	0							
Field Moisture Content (%)	23.5							
Field Moisture Content Method	AS 1289.2.1.1							
Field Wet Density (t/m³)	1.99							
Field Dry Density (t/m³)	1.61							
Peak Converted Wet Density (t/m³)	2.04							
Optimum Moisture Content (%)	21.5							
Compactive Effort	Standard							
Moisture Ratio (%)	108.0							
Moisture Variation (%)	1.5 wet							
Hilf Density Ratio (%)	97.5							

\mathbf{c}	m	m	01	+-
Cc)	ш	ei	เเธ





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01807

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

AC MEA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield
12719 (Senior Technician)
Site Number: 12712 Date of Issue: 15/09/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (1% Dry to 3% Wet of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Silty Clay traces of Gravel

Sample Data								
Sample ID	S22DS-07085							
Field Sample ID	1							
Client Sample ID	4							
Date Tested	12/09/2022							
Time Tested	15:45							
E:	2554.661 (356381)							
N:	201.159 (5781044)							
EL:	40.497							
Lot / Layer:	4230 / 1							
Field and Laboratory Data								
Depth of Test (mm)	175							
Depth of Layer (mm)	200							
AS Sieve Size (mm)	19.0							
Oversize Wet (%)	0							
Field Moisture Content (%)	20.9							
Field Moisture Content Method	AS 1289.2.1.1							
Field Wet Density (t/m³)	2.07							
Field Dry Density (t/m³)	1.71							
Peak Converted Wet Density (t/m³)	2.08							
Optimum Moisture Content (%)	18.5							
Compactive Effort	Standard							
Moisture Ratio (%)	111.5							
Moisture Variation (%)	2.0 wet							
Hilf Density Ratio (%)	99.5							

\mathbf{c}	m	m	01	+-
Cc)	ш	ei	เเธ





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01914

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate - Stage 40

Project No.: 3807351.040

Order No.: CG Request No.:

TRN: Lot No.:

Iac MRA NATA

NATA

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (OMC to 3% Wet)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Imported Material: Silty Clay

Sample Data						
Sample ID	S22DS-07625	S22DS-07626	S22DS-07627	S22DS-07628	S22DS-07629	S22DS-07630
Field Sample ID	1	2	3	4	5	6
Client Sample ID	24	25	26	27	28	29
Date Tested	27/09/2022	27/09/2022	27/09/2022	27/09/2022	27/09/2022	27/09/2022
Time Tested		11:30	12:15			
E:	2436.500	2437.110	2543.870	2475.164	2478.784	2446.110
N:	253.130	229.760	217.730	327.344	354.7317	290720
EL:	42.17	41.90	40.95	43.62	44.30	41.805
Lot / Layer:	4020 / 2	4028 / 2	4225 - 2	4019 / -	40.17 / -	4003
						Retest
Field and Laboratory Data						
Depth of Test (mm)	175	175	175	175	175	175
Depth of Layer (mm)	200	200	200	200	200	200
AS Sieve Size (mm)	19.0	19.0	19.0	19.0	19.0	19.0
Oversize Wet (%)	0	0	0	0	0	0
Field Moisture Content (%)	16.7	24.5	19.4	23.4	17.5	19.6
Field Moisture Content Method	AS 1289.2.1.1					
Field Wet Density (t/m³)	2.08	2.01	1.99	1.98	2.02	2.03
Field Dry Density (t/m³)	1.78	1.61	1.67	1.60	1.72	1.70
Peak Converted Wet Density (t/m³)	2.00	1.99	2.14	2.06	1.91	2.09
Optimum Moisture Content (%)	17.5	22.0	17.5	20.5	22.5	19.0
Compactive Effort	Standard	Standard	Standard	Standard	Standard	Standard
Moisture Ratio (%)	95.0	111.0	110.0	113.5	78.0	103.0
Moisture Variation (%)	1.0 dry	2.5 wet	1.5 wet	2.5 wet	4.5 dry	0.5 wet
Hilf Density Ratio (%)	104.0	100.5	93.0	96.0	105.5	97.5

Comments





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01926

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

ATA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements:

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Clay

Sample Data				
Sample ID	S22DS-07673			
Field Sample ID	1			
Client Sample ID	5			
Date Tested	28/09/2022			
E:	2465.24			
N:	235.48			
EL:	42.30			
Lot / Layer:	4225 / FSL			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	16.0			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.02			
Field Dry Density (t/m³)	1.74			
Peak Converted Wet Density (t/m³)	2.13			
Optimum Moisture Content (%)	16.5			
Compactive Effort	Standard			
Moisture Ratio (%)	97.5			
Moisture Variation (%)	0.5 dry			
Hilf Density Ratio (%)	95.0			

	$\overline{}$	m	m	^	n	+0
U	U	ш	m	E	ш	เอ





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01937

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

Accreditation Number:

NATA

Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield (Senior Technician)

12719 Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Clay

Sample Data					
Sample ID	S22DS-07714	S22DS-07715	S22DS-07716		
Field Sample ID	1	2	3		
Client Sample ID	6	7	8		
Date Tested	29/09/2022	29/09/2022	29/09/2022		
E:	2555.03	2528.16	2494.79		
N:	200.05	204.40	205.15		
RL:	40.71	41.73	42.23		
Lot / Layer:	4230 / 2	4228 / 2	4227 / 2		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	17.5	17.7	17.4		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.00	1.98	2.00		
Field Dry Density (t/m³)	1.70	1.68	1.71		
Peak Converted Wet Density (t/m³)	2.09	2.09	2.09		
Optimum Moisture Content (%)	17.5	17.5	17.5		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	101.0	101.0	100.5		
Moisture Variation (%)	0.0	0.0	0.0		
Hilf Density Ratio (%)	95.5	95.0	96.0		

Comments





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01961

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: ilac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements:

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Imported Material: Clay

0 I - D - (-					
Sample Data					
Sample ID	S22DS-07794	S22DS-07795	S22DS-07796		
Field Sample ID	1	2	3		
Client Sample ID	9	10	11		
Date Tested	30/09/2022	30/09/2022	30/09/2022		
E:	2543.89	2465.65	2493.23		
N:	217.72	234.52	217.77		
RL:	40.98	42.32	42.32		
Lot / Layer:	4225 / 2	4225 / 3	4226 / 3		
	Retest of S22DS-07627				
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	16.7	18.3	28.4		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.06	2.06	2.09		
Field Dry Density (t/m³)	1.77	1.74	1.62		
Peak Converted Wet Density (t/m³)	2.14	2.08	2.13		
Optimum Moisture Content (%)	16.5	18.5	28.5		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	100.5	100.5	100.0		
Moisture Variation (%)	0.0	0.0	0.0		
Hilf Density Ratio (%)	96.5	99.0	98.0		

Comments





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01962

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S22DS-07797			
Field Sample ID	1			
Client Sample ID	12			
Date Tested	1/10/2022			
Time Tested	01:17			
E:	2528.55 (356354)			
N:	221.42 (5781066)			
EL:	41.69			
Lot:	4228			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	16.7			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.07			
Field Dry Density (t/m³)	1.77			
Peak Converted Wet Density (t/m³)	2.06			
Optimum Moisture Content (%)	17.0			
Compactive Effort	Standard			
Moisture Ratio (%)	98.0			
Moisture Variation (%)	0.5 dry			
Hilf Density Ratio (%)	100.5			

	_	100	m	0	nto
C	U	ш	ш	е	nts





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01974

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory; M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Project:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Clay with traces of Gravel

Sample Data				
Sample ID	S22DS-07831	S22DS-07832		
Field Sample ID	1	2		
Client Sample ID	13	14		
Date Tested	3/10/2022	3/10/2022		
Time Tested	11:45	11:30		
E:	-	2556.789		
N:	-	215.951		
EL:	-	40.835		
Lot / Layer:	4229 / 2	4230 / 3		
	Retest of S22DS-07627			
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	17.4	15.5		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.07	2.05		
Field Dry Density (t/m³)	1.76	1.78		
Peak Converted Wet Density (t/m³)	2.07	2.13		
Optimum Moisture Content (%)	17.5	16.0		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	98.5	97.5		
Moisture Variation (%)	0.0	0.5 dry		
Hilf Density Ratio (%)	100.0	96.5		

\sim	-	-		-1-
Co	144	144	T 🖴	116
\sim	ш	ш		





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS01991

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025

p (

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Site Number: 12712 | Date of Issue: 20/10/2022

Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Silty Clay

Sample Data				
Sample ID	S22DS-07904			
Field Sample ID	1			
Client Sample ID	15			
Date Tested	4/10/2022			
Time Tested	15:15			
E:	2498.040 (356320)			
N:	220.025 (5781065)			
EL:	42.360			
Lot / Layer:	4226 / 4			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	14.0			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.08			
Field Dry Density (t/m³)	1.82			
Peak Converted Wet Density (t/m³)	2.15			
Optimum Moisture Content (%)	14.0			
Compactive Effort	Standard			
Moisture Ratio (%)	100.0			
Moisture Variation (%)	0.0			
Hilf Density Ratio (%)	96.5			

_	-	-	_	-	4-
	144	m		101	
v	ш	ш	v	ш	





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02001

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

ber: Approved Signatory: M. Longfield

Accreditation Number: Approved Signatory: M. Longfield
(Senior Technician)
Site Number: 12712 Date of Issue: 20/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Silty Clay

Sample Data				
Sample ID	S22DS-07934			
Field Sample ID	1			
Client Sample ID	16			
Date Tested	5/10/2022			
Time Tested	14:11			
E:	2543.700 (356367)			
N:	210.030 (5781054)			
EL:	41.40			
Lot / Layer:	4229 / 4			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	15.9			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.12			
Field Dry Density (t/m³)	1.83			
Peak Converted Wet Density (t/m³)	2.12			
Optimum Moisture Content (%)	16.0			
Compactive Effort	Standard			
Moisture Ratio (%)	98.5			
Moisture Variation (%)	0.0			
Hilf Density Ratio (%)	100.0			

\mathbf{c}	1	m	01	+-
Cc	Ш	ш	ei	เเธ





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02085

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 25/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S22DS-08284	S22DS-08285		
Field Sample ID	1	2		
Client Sample ID	17	18		
Date Tested	19/10/2022	19/10/2022		
Time Tested	11:30	11:40		
E:	205.920	245.014		
N:	2590.810	2598.869		
EL:	39.590	41.46		
Lot / Layer:	4232 / -	4233 / -		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	26.1	23.6		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	1.96	1.94		
Field Dry Density (t/m³)	1.55	1.57		
Peak Converted Wet Density (t/m³)	1.90	1.99		
Optimum Moisture Content (%)	27.0	23.5		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	97.0	99.5		
Moisture Variation (%)	1.0 dry	0.0		
Hilf Density Ratio (%)	102.5	97.5		

Comments





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02111

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IAC MRA NATA

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Site Number: 12712 Date of Issue: 25/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Clay

Sample Data				
Sample ID	S22DS-08379	S22DS-08380		
Field Sample ID	1	2		
Client Sample ID	18	19		
Date Tested	21/10/2022	21/10/2022		
Time Tested	10:00	10:15		
E:	2581.99	2593.18		
N:	191.31	238.28		
RL:	39.96	40.53		
Lot:	4232	4233		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	20.8	17.2		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	1.99	1.99		
Field Dry Density (t/m³)	1.65	1.70		
Peak Converted Wet Density (t/m³)	2.03	2.10		
Optimum Moisture Content (%)	21.0	17.0		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	99.5	101.0		
Moisture Variation (%)	0.0	0.0		
Hilf Density Ratio (%)	98.0	94.5		

Comments





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02144

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

- Testing

 \mathcal{A}

Accreditation Number: Approved Signatory: M. Longfield
12719 (Senior Technician)
Site Number: 12712 Date of Issue: 26/10/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Clay with traces of Gravel

Sample Data					
Sample ID	S22DS-08579	S22DS-08580	S22DS-08581		
Field Sample ID	1	2	3		
Client Sample ID	20	21	23		
Date Tested	24/10/2022	24/10/2022	24/10/2022		
Time Tested	09:45	09:57	12:58		
E:	2572.86 (356397)	2590.98 (356415)	- (356417)		
N:	199.37 (5781038)	229.53 (5781068)	- (5781083)		
EL:	40.49	40.58	-		
Lot / Layer:	4231 / 3	4233 / 3	-		
			Retest of S22DS-08380		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	16.5	16.1	14.6		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.01	2.05	2.07		
Field Dry Density (t/m³)	1.72	1.77	1.80		
Peak Converted Wet Density (t/m³)	2.07	2.09	2.09		
Optimum Moisture Content (%)	17.0	16.5	15.0		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	97.5	98.5	98.5		
Moisture Variation (%)	0.5 dry	0.5 dry	0.0		
Hilf Density Ratio (%)	97.0	98.5	99.0		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02198

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 15/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S22DS-08770	S22DS-08771		
Field Sample ID	1	2		
Client Sample ID	24	25		
Date Tested	8/11/2022	8/11/2022		
Time Tested	07:25	07:35		
E:	2588.55 (356411)	2583.77 (356407)		
N:	200.61 (5781043)	242.33 (5781084)		
EL:	40.32	41.16		
Lot / Layer:	4232 / 4	4234 / 4		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	15.9	16.6		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.08	2.07		
Field Dry Density (t/m³)	1.79	1.77		
Peak Converted Wet Density (t/m³)	2.14	2.12		
Optimum Moisture Content (%)	13.5	16.5		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	117.0	101.0		
Moisture Variation (%)	2.5 wet	0.0		
Hilf Density Ratio (%)	97.0	98.0		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02220

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project: Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

NATA

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician)

Site Number: 12712 Date of Issue: 15/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data					
Sample ID	S22DS-08881	S22DS-08882	S22DS-08883		
Field Sample ID	1	2	3		
Client Sample ID	26	27	28		
Date Tested	11/11/2022	11/11/2022	11/11/2022		
Time Tested	13:40	13:50	14:00		
E:	2582.95 (356409)	2588.55 (356415)	2597.97 (356423)		
N:	293.300 (5781136)	327.79 (5781173)	351.58 (5871195)		
EL:	41.74	42.70	43.25		
Lot / Layer:	4202 / 1	4204 / 1	4206 / 1		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	23.0	17.5	17.8		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.04	1.99	2.05		
Field Dry Density (t/m³)	1.66	1.69	1.74		
Peak Converted Wet Density (t/m³)	1.96	2.00	2.05		
Optimum Moisture Content (%)	24.5	20.0	18.5		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	94.0	88.0	97.5		
Moisture Variation (%)	1.5 dry	2.5 dry	0.5 dry		
Hilf Density Ratio (%)	104.0	99.5	100.0		





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02218

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 15/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location: Stage 42

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Clay

Material: Clay Trace Gravel

Sample Data									
Sample ID	S22DS-08876								
Field Sample ID	1								
Date Tested	12/11/2022								
Time Tested	11:57								
E:	2591.56 (356416)								
N:	236.88 (5781079)								
EL:	41.07								
Lot / Layer:	4233 / 5								
Field and Laboratory Data									
Depth of Test (mm)	175								
Depth of Layer (mm)	200								
AS Sieve Size (mm)	19.0								
Oversize Wet (%)	0								
Field Moisture Content (%)	21.7								
Field Moisture Content Method	AS 1289.2.1.1								
Field Wet Density (t/m³)	2.00								
Field Dry Density (t/m³)	1.64								
Peak Converted Wet Density (t/m³)	1.98								
Optimum Moisture Content (%)	22.0								
Compactive Effort	Standard								
Moisture Ratio (%)	98.0								
Moisture Variation (%)	0.5 dry								
Hilf Density Ratio (%)	101.0								

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02254

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

N

Accreditation Number: Approved Signatory: M. Longfield
12719 (Senior Technician)
Site Number: 12712 Date of Issue: 30/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Sandy Clay

Sample Data								
Sample ID	S22DS-09011	S22DS-09012	S22DS-09013					
Field Sample ID	1	2	3					
Client Sample ID	30	31	32					
Date Tested	16/11/2022	16/11/2022	16/11/2022					
Time Tested	13:57	14:14	14:23					
E:	2609.13 (356431)	2602.83 (356425)	2597.18 (356420)					
N:	329.50 (5781173)	305.52 (5781149)	280.18 (5781122)					
EL:	42.54	425.05	41.44					
Lot / Layer :	4205 / 2	4203 / 2	4201 / 2					
Field and Laboratory Data								
Depth of Test (mm)	175	175	175					
Depth of Layer (mm)	200	200	200					
AS Sieve Size (mm)	19.0	19.0	19.0					
Oversize Wet (%)	0	0	0					
Field Moisture Content (%)	24.1	24.2	22.6					
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1					
Field Wet Density (t/m³)	1.94	2.00	1.97					
Field Dry Density (t/m³)	1.56	1.61	1.61					
Peak Converted Wet Density (t/m³)	1.99	2.00	2.04					
Optimum Moisture Content (%)	24.5	24.0	22.5					
Compactive Effort	Standard	Standard	Standard					
Moisture Ratio (%)	99.5	100.5	100.5					
Moisture Variation (%)	0.0	0.0	0.0					
Hilf Density Ratio (%)	97.5	100.0	96.5					





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02275

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42 **Project No.:** 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician)

Site Number: 12712 Date of Issue: 30/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location: Stage 42

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data					
Sample ID	S22DS-09110	S22DS-09111	S22DS-09112	S22DS-09113	
Field Sample ID	1	2	3	4	
Client Sample ID	32	33	34	35	
Date Tested	18/11/2022	18/11/2022	18/11/2022	18/11/2022	
Time Tested	13:03	13:12	13:21	13:29	
E:	2601.69 (356425)	2597.18 (356420)	2590.44 (356412)	2587.08 (356409)	
N:	358.16 (5781183)	346.36 (5781183)	324.10 (57811645)	298.31 (5781138)	
EL:	43.57	43.37	42.98	42.27	
Lot / Layer	4207 / 3	4206 / 3	4204 / 3	4202 / 3	
Field and Laboratory Data					
Depth of Test (mm)	175	175	175	175	
Depth of Layer (mm)	200	200	200	200	
AS Sieve Size (mm)	19.0	19.0	19.0	19.0	
Oversize Wet (%)	0	0	0	0	
Field Moisture Content (%)	13.7	15.8	20.1	21.6	
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	
Field Wet Density (t/m³)	2.10	2.06	2.04	1.97	
Field Dry Density (t/m³)	1.84	1.77	1.70	1.62	
Peak Converted Wet Density (t/m³)	2.12	2.10	2.03	2.00	
Optimum Moisture Content (%)	14.5	16.0	20.0	21.5	
Compactive Effort	Standard	Standard	Standard	Standard	
Moisture Ratio (%)	95.0	99.0	100.5	100.0	
Moisture Variation (%)	0.5 dry	0.0	0.0	0.0	
Hilf Density Ratio (%)	99.0	98.0	100.5	98.5	





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02310

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accreditation Number: Approved Signatory: M. Longfield
12719 (Senior Technician)
Site Number: 12712 Date of Issue: 30/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Sandy Clay

Sample Data					
Sample ID	S22DS-09334	S22DS-09335	S22DS-09336		
Field Sample ID	1	2	3		
Client Sample ID	36	37	38		
Date Tested	23/11/2022	23/11/2022	23/11/2022		
Time Tested	14:10	14:15	14:22		
E:	2595.41 (356416)	2592.06 (356413)	2594.77 (356415)		
N:	336.42 (5781178)	311.33 (5781153)	273.91 (5781116)		
EL:	43.13	42.80	41.30		
Lot / Layer:	4205 / 4	4203 / 4	4201 / 4		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	17.9	20.5	19.5		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.06	1.97	2.01		
Field Dry Density (t/m³)	1.75	1.64	1.69		
Peak Converted Wet Density (t/m³)	1.99	1.93	1.97		
Optimum Moisture Content (%)	19.0	21.5	21.5		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	95.5	96.0	91.5		
Moisture Variation (%)	1.0 dry	1.0 dry	2.0 dry		
Hilf Density Ratio (%)	103.0	102.0	102.5		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02334

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

12719

NATA

Approved Signatory: M. Longfield

Accredited for compliance with ISO/IEC 17025

Accreditation Number: (Senior Technician) Site Number: 12712 Date of Issue: 30/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Project:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Sandy Clay, Traces of Silt & Gravel

Sample Data					
Sample ID	S22DS-09409	S22DS-09410	S22DS-09411		
Field Sample ID	1	2	3		
Client Sample ID	61	62	63		
Date Tested	26/11/2022	26/11/2022	26/11/2022		
Time Tested	08:35	08:45	08:55		
E:	2564.21 (356387)	2554.29 (356376)	2575.53 (356400)		
N:	296.72 (5781139)	287.54 (5781131)	283.04 (5781125)		
EL:	42.68	42.43	42.24		
Lot / Layer:	4124 / 6	4125 / 5	4127 / 5		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	20.5	22.2	23.4		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.06	2.03	2.00		
Field Dry Density (t/m³)	1.71	1.66	1.62		
Peak Converted Wet Density (t/m³)	1.92	1.89	1.97		
Optimum Moisture Content (%)	23.5	25.5	24.5		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	86.5	87.5	96.0		
Moisture Variation (%)	3.0 dry	3.0 dry	1.0 dry		
Hilf Density Ratio (%)	107.5	107.5	101.0		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02336

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 41

Project No.: 3807351.041

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 30/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data								
Sample ID	S22DS-09412	S22DS-09413	S22DS-09414					
Field Sample ID	1	2	3					
Client Sample ID	39	40	41					
Date Tested	26/11/2022	26/11/2022	26/11/2022					
Time Tested	09:00	11:15	11:25					
E:	2594.66 (356416)	2653.84 (356472)	2642.44 (356460)					
N:	273.36 (5781114)	300.33 (5781145)	272.78 (5781115)					
EL:	41.42	41.17	40.63					
Lot / Layer:	4201 / 5	4214 / 1	4216 / 1					
Field and Laboratory Data								
Depth of Test (mm)	175	175	175					
Depth of Layer (mm)	200	200	200					
AS Sieve Size (mm)	19.0	19.0	19.0					
Oversize Wet (%)	0	0	0					
Field Moisture Content (%)	16.8	18.0	17.7					
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1					
Field Wet Density (t/m³)	2.02	1.98	1.99					
Field Dry Density (t/m³)	1.73	1.68	1.69					
Peak Converted Wet Density (t/m³)	2.08	2.11	2.07					
Optimum Moisture Content (%)	17.0	18.0	17.5					
Compactive Effort	Standard	Standard	Standard					
Moisture Ratio (%)	97.5	99.5	101.0					
Moisture Variation (%)	0.5 dry	0.0	0.0					
Hilf Density Ratio (%)	97.0	94.0	96.5					





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02363

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

A NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 2/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Clay

Sample Data				
Sample ID	S22DS-09529	S22DS-09530		
-				
Field Sample ID	1	2		
Client Sample ID	42	3		
Date Tested	29/11/2022	29/11/2022		
Time Tested	14:45	14:58		
Lot / Layer:	4214 / 1	4201 / 5		
	Retest of S22DS-09410	Retest of S22DS-09409		
Field and Laboratory Data	S22DS-09410	S22DS-09409		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	22.3	17.6		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	1.90	2.02		
Field Dry Density (t/m³)	1.56	1.72		
Peak Converted Wet Density (t/m³)	1.92	2.09		
Optimum Moisture Content (%)	25.0	18.0		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	89.5	98.5		
Moisture Variation (%)	2.5 dry	0.0		
Hilf Density Ratio (%)	99.5	97.0		

	_	-	_		_		~	-
C		10	4 I		Ш	211	ı	
•	v	ш	ш	ш	ш	•	ш	





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02375

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: ilac-MRA



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 2/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements:

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 AS1289.1.2.1 Clause 6.4 (b) Sampling Method:

Source: Onsite Material: Sandy Clay

Sample Data				
Sample ID	S22DS-09582	S22DS-09583		
Field Sample ID	1	2		
Client Sample ID	44	45		
Date Tested	30/11/2022	30/11/2022		
Time Tested	08:00	12:26		
E:	2641.89 (356468)	2629.25 (356454)		
N:	324.20 (5781165)	316.00 (5781156)		
EL:	41.75	42.16		
Lot / Layer:	4212 / 1	4213 / 2		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	16.3	19.6		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	1.96	2.06		
Field Dry Density (t/m³)	1.69	1.72		
Peak Converted Wet Density (t/m³)	1.96	1.94		
Optimum Moisture Content (%)	18.5	22.0		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	88.5	89.5		
Moisture Variation (%)	2.0 dry	2.0 dry		
Hilf Density Ratio (%)	100.0	106.0		

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02381

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 19/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data				
Sample ID	S22DS-09601			
Field Sample ID	1			
Client Sample ID	46			
Date Tested	1/12/2022			
Time Tested	07:39			
E:	2634.41 (356458)			
N:	287.76 (5781131)			
EL:	41.36			
Lot / Layer:	4215 / 2			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Wet Density (t/m³)	1.98			
Peak Converted Wet Density (t/m³)	1.89			
Compactive Effort	Standard			
Moisture Variation (%)	2.5 dry			
Hilf Density Ratio (%)	104.5			

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02398

This report replaces all previous issues of report no 'HDR:W22DS02398'.

Issue No: 2





Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Site Number: 12712 Date of Issue: 19/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

Sample Details

Location: Stage 42

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95%

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Clay

Material:

Sample Data				
Sample ID	S22DS-09646			
Field Sample ID	1			
Client Sample ID	47			
Date Tested	2/12/2022			
Time Tested	07:26			
Location	Lot: 4213			
	Retest 09583			
	from 30/11/22			
Soil Description	Sandy Clay			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
Field Moisture Content (%)	25.7			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.01			
Field Dry Density (t/m³)	1.60			
Peak Converted Wet Density (t/m³)	1.88			
Optimum Moisture Content (%)	28.0			
Compactive Effort	Standard			
Moisture Ratio (%)	91.5			
Moisture Variation (%)	2.5 dry			
Hilf Density Ratio (%)	107.5			

\sim	-	-		-1-
Co	144	144	T 🖴	116
\sim	ш	ш		



Project:



Dandenong South ACN 143 009 330

25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02406

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: Iac-MRA

NATA

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician) Site Number: 12712 Date of Issue: 19/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location: Stage 42

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95%

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Clay

Material:

Sample Data								
S22DS-09666	S22DS-09667	S22DS-09668						
1	2	3						
5/12/2022	5/12/2022	5/12/2022						
09:34	09:14	15:43						
2635.694 (356459)	2635.614 (356458)	2631.483 (356457)						
301.726 (5781142)	274.613 (5781117)	333.879 (5781174)						
41.820	40.939	42.541						
4214/3	4216/3	4212/3						
175	175	175						
200	200	200						
16.6	13.9	15.9						
AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1						
2.04	2.12	2.09						
1.75	1.86	1.80						
1.91	1.99	1.99						
21.5	17.0	19.0						
Standard	Standard	Standard						
77.0	82.0	84.0						
5.0 dry	3.0 dry	3.0 dry						
107.0	106.5	105.0						
	1 5/12/2022 09:34 2635.694 (356459) 301.726 (5781142) 41.820 4214/3 175 200 16.6 AS 1289.2.1.1 2.04 1.75 1.91 21.5 Standard 77.0 5.0 dry	1 2 5/12/2022 5/12/2022 09:34 09:14 2635.694 (356459) 2635.614 (356458) 301.726 (5781142) 274.613 (5781117) 41.820 40.939 4214/3 4216/3 175 175 200 200 16.6 13.9 AS 1289.2.1.1 AS 1289.2.1.1 2.04 2.12 1.75 1.86 1.91 1.99 21.5 17.0 Standard Standard 77.0 82.0 5.0 dry 3.0 dry	1 2 3 5/12/2022 5/12/2022 5/12/2022 09:34 09:14 15:43 2635.694 (356459) 2635.614 (356458) 2631.483 (356457) 301.726 (5781142) 274.613 (5781117) 333.879 (5781174) 41.820 40.939 42.541 4214/3 4216/3 4212/3 175 175 175 200 200 200 16.6 13.9 15.9 AS 1289.2.1.1 AS 1289.2.1.1 AS 1289.2.1.1 2.04 2.12 2.09 1.75 1.86 1.80 1.91 1.99 1.99 21.5 17.0 19.0 Standard Standard Standard 77.0 82.0 84.0 5.0 dry 3.0 dry 3.0 dry	1 2 3 5/12/2022 5/12/2022 5/12/2022 09:34 09:14 15:43 2635.694 (356459) 2635.614 (356458) 2631.483 (356457) 301.726 (5781142) 274.613 (5781117) 333.879 (5781174) 41.820 40.939 42.541 4214/3 4216/3 4212/3 175 175 175 200 200 200 16.6 13.9 15.9 AS 1289.2.1.1 AS 1289.2.1.1 AS 1289.2.1.1 2.04 2.12 2.09 1.75 1.86 1.80 1.91 1.99 1.99 21.5 17.0 19.0 Standard Standard Standard 77.0 82.0 84.0 5.0 dry 3.0 dry 3.0 dry	1 2 3 5/12/2022 5/12/2022 5/12/2022 09:34 09:14 15:43 2635.694 (356459) 2635.614 (356458) 2631.483 (356457) 301.726 (5781142) 274.613 (5781117) 333.879 (5781174) 41.820 40.939 42.541 4214/3 4216/3 4212/3 175 175 175 200 200 200 16.6 13.9 15.9 AS 1289.2.1.1 AS 1289.2.1.1 AS 1289.2.1.1 2.04 2.12 2.09 1.75 1.86 1.80 1.91 1.99 1.99 21.5 17.0 19.0 Standard Standard Standard 77.0 82.0 84.0 5.0 dry 3.0 dry 3.0 dry			





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02422

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

A NATA

- Testing

Accredited for compliance with ISO/IEC 17025

~

Accreditation Number: Approved Signatory: M. Longfield
12719 (Senior Technician)
Site Number: 12712 Date of Issue: 19/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Sandy Clay

-					
Sample Data					
Sample ID	S22DS-09729	S22DS-09730	S22DS-09731		
Field Sample ID	1	2	3		
Client Sample ID	51	52	53		
Date Tested	7/12/2022	7/12/2022	7/12/2022		
Time Tested	12:50	13:58	14:03		
E:	2641.10 (356462)	-	2638.51 (356461)		
N:	316.21 (5781162)	-	286.73 (5781129)		
EL:	42.25	-	41.63		
Lot / Layer:	4213 / 4	4214 / 3	4215 / 4		
		Retest of S22DS-09666			
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Wet Density (t/m³)	2.05	1.99	2.05		
Peak Converted Wet Density (t/m³)	1.98	2.03	2.11		
Compactive Effort	Standard	Standard	Standard		
Moisture Variation (%)	2.5 dry	0.0	0.5 dry		
Hilf Density Ratio (%)	103.5	98.0	97.0		

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02436

This report replaces all previous issues of report no 'HDR:W22DS02436'.

Issue No: 2





Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician)

- Testing

Site Number: 12712 Date of Issue: 19/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.:

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data					
Sample ID	S22DS-09822	S22DS-09823	S22DS-09824		
Field Sample ID	1	2	3		
Client Sample ID	54	55	56		
Date Tested	8/12/2022	8/12/2022	8/12/2022		
Time Tested	14:02	14:08	15:45		
E:	2651.263 (356476)	2655.938 (356480)	2641.596 (356464)		
N:	297.963 (5781143)	329.035 (5781175)	273.556 (5781118)		
EL:	41.687	42.092	41.379		
Lot / Layer:	4214 / 5	4212 / 5	4216 / 5		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	15.5	15.0	18.5		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.02	2.01	1.97		
Field Dry Density (t/m³)	1.75	1.75	1.66		
Peak Converted Wet Density (t/m³)	2.06	2.12	2.03		
Optimum Moisture Content (%)	16.0	15.5	19.0		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	98.0	97.0	97.0		
Moisture Variation (%)	0.5 dry	0.5 dry	0.5 dry		
Hilf Density Ratio (%)	98.0	95.0	97.5		





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02514

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

NATA

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 22/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Clay

Sample Data						
Sample ID	S22DS-10052	S22DS-10053	S22DS-10054	S22DS-10055	S22DS-10056	
Field Sample ID	1	2	3	4	5	
Client Sample ID	57	58	59	60	61	
Date Tested	19/12/2022	19/12/2022	19/12/2022	19/12/2022	19/12/2022	
Time Tested	08:34	08:45	08:55	09:21	08:29	
E:	2645.42 (356469)	2636.03 (356458)	2633.86 (3564757)	2640.21 (356462)	2644.28 (356464)	
N:	313.11 (5781156)	287.39 (5781130)	276.21 (5781119)	299.38 (5781145)	329.53 (5781177)	
EL:	42.27	41.84	41.69	42.12	42.81	
Lot / Layer:	4213 / 6	4215 / 6	4216 / 7	4214 / 7	4212 / 7	
Field and Laboratory Data						
Depth of Test (mm)	175	175	175	175	175	
Depth of Layer (mm)	200	200	200	200	200	
AS Sieve Size (mm)	19.0	19.0	19.0	19.0	19.0	
Oversize Wet (%)	0	0	0	0	0	
Field Moisture Content (%)	17.8	21.1	19.3	17.0	16.9	
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	
Field Wet Density (t/m³)	2.01	2.07	2.07	2.07	2.04	
Field Dry Density (t/m³)	1.71	1.71	1.73	1.77	1.74	
Peak Converted Wet Density (t/m³)	2.05	2.01	2.03	2.03	1.91	
Optimum Moisture Content (%)	18.0	21.5	20.0	19.5	21.5	
Compactive Effort	Standard	Standard	Standard	Standard	Standard	
Moisture Ratio (%)	98.5	98.5	96.0	86.5	79.0	
Moisture Variation (%)	0.5 dry	0.5 dry	1.0 dry	2.5 dry	4.5 dry	
Hilf Density Ratio (%)	98.0	102.5	102.0	102.0	106.5	





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02539

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA **NATA**

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 22/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Project:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S22DS-10186	S22DS-10187		
Field Sample ID	1	2		
Client Sample ID	62	63		
Date Tested	20/12/2022	20/12/2022		
Time Tested	11:55	12:01		
E:	2630.23 (356453)	2629.23 (356452)		
N:	256.89 (5781103)	230.04 (5781073)		
EL:	40.61	39.97		
Lot / Layer:	4217 / 1	4219 / 1		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	14.8	15.1		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.07	2.08		
Field Dry Density (t/m³)	1.80	1.81		
Peak Converted Wet Density (t/m³)	2.15	2.13		
Optimum Moisture Content (%)	15.0	15.0		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	99.5	99.0		
Moisture Variation (%)	0.0	0.0		
Hilf Density Ratio (%)	96.0	97.5		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W22DS02556

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 23/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Sandy/Silty Clay

Sample Data					
Sample ID	S22DS-10268	S22DS-10269	S22DS-10270	S22DS-10271	
Field Sample ID	1	2	3	4	
Client Sample ID	64	65	66	67	
Date Tested	21/12/2022	21/12/2022	21/12/2022	21/12/2022	
Time Tested	07:25	07:33	14:55	15:00	
E:	-	2643.72 (356466)	2625.39 (356449)	2620.69 (356443)	
N:	-	329.06 (5781172)	243.23 (5781087)	214.22 (5781057)	
EL:	-	42.86	40.52	39.88	
Lot / Layer:	-/7	4212 / 8	4218 / 2	4220 / 2	
	Retest of S22DS-10056				
Field and Laboratory Data					
Depth of Test (mm)	175	175	175	175	
Depth of Layer (mm)	200	200	200	200	
AS Sieve Size (mm)	19.0	19.0	19.0	19.0	
Oversize Wet (%)	0	0	0	0	
Field Moisture Content (%)	18.5	17.9	17.1	13.7	
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	
Field Wet Density (t/m³)	2.00	2.00	1.99	1.99	
Field Dry Density (t/m³)	1.69	1.69	1.69	1.75	
Peak Converted Wet Density (t/m³)	1.96	1.99	2.09	2.09	
Optimum Moisture Content (%)	20.5	18.5	17.0	13.5	
Compactive Effort	Standard	Standard	Standard	Standard	
Moisture Ratio (%)	90.5	95.5	101.0	100.5	
Moisture Variation (%)	2.0 dry	1.0 dry	0.0	0.0	
Hilf Density Ratio (%)	102.0	100.5	95.0	95.0	





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00001

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 9/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Comple Date								
Sample Data								
Sample ID	S23DS-00001	S23DS-00002	S23DS-00003					
Field Sample ID	1	2	3					
Date Tested	3/01/2023	3/01/2023	3/01/2023					
Time Tested	14:40	15:10	11:10					
E:	356450	356448	35469					
N:	5781102	5781070	5781185					
RL:	41.01	40.34	-					
Lot / Layer:	4217 / -	4219 / -	4212 / -					
			Retest of S22DS-10056					
Field and Laboratory Data								
Depth of Test (mm)	175	175	175					
Depth of Layer (mm)	200	200	200					
AS Sieve Size (mm)	19.0	19.0	19.0					
Oversize Wet (%)	0	0	0					
Field Moisture Content (%)	13.8	14.7	14.1					
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1					
Field Wet Density (t/m³)	2.00	2.04	1.98					
Field Dry Density (t/m³)	1.76	1.78	1.74					
Peak Converted Wet Density (t/m³)	2.08	2.14	2.10					
Optimum Moisture Content (%)	16.0	14.5	14.5					
Compactive Effort	Standard	Standard	Standard					
Moisture Ratio (%)	86.0	100.5	97.5					
Moisture Variation (%)	2.0 dry	0.0	0.5 dry					
Hilf Density Ratio (%)	96.0	95.5	94.5					





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00004

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 9/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data					
Sample ID	S23DS-00006	S23DS-00007	S23DS-00008	S23DS-00009	
Field Sample ID	1	2	3	4	
Date Tested	4/01/2023	4/01/2023	4/01/2023	4/01/2023	
Time Tested	11:30	11:00	14:45	16:00	
E:	356425	356465	356462	356462	
N:	5781118	5781187	5781078	5781115	
EL:	41.68	42.80	40.64	41.37	
Lot:	4201	4212	4218	4216	
		retest 00003			
Field and Laboratory Data					
Depth of Test (mm)	175	175	175	175	
Depth of Layer (mm)	200	200	200	200	
AS Sieve Size (mm)	19.0	19.0	19.0	19.0	
Oversize Wet (%)	0	0	0	0	
Field Moisture Content (%)	13.3	11.8	14.4	15.5	
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	
Field Wet Density (t/m³)	2.06	2.08	2.10	2.11	
Field Dry Density (t/m³)	1.82	1.86	1.83	1.82	
Peak Converted Wet Density (t/m³)	2.16	2.18	2.13	2.13	
Optimum Moisture Content (%)	13.5	12.0	15.0	15.5	
Compactive Effort	Standard	Standard	Standard	Standard	
Moisture Ratio (%)	100.0	98.5	97.5	100.0	
Moisture Variation (%)	0.0	0.0	0.5 dry	0.0	
Hilf Density Ratio (%)	95.5	95.5	98.5	99.0	





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00009

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: Iac-MRA



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 9/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Project:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 AS1289.1.2.1 Clause 6.4 (b) Sampling Method:

Source: Onsite Clay

Material:

Sample Data					
Sample ID	S23DS-00025	S23DS-00026	S23DS-00027		
Field Sample ID	1	2	3		
Date Tested	5/01/2023	5/01/2023	5/01/2023		
Time Tested	13:00	13:57	14:00		
E:	356451	356467	356455		
N:	5781055	5781098	5781073		
LOT:	4220	4217	4219		
EL:	40.06	41.08	40.49		
Soil Description	Sandy Clay	Sandy Clay	Sandy Clay		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	14.1	16.0	16.0		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.12	2.13	2.14		
Field Dry Density (t/m³)	1.86	1.84	1.85		
Peak Converted Wet Density (t/m³)	2.13	2.12	2.11		
Optimum Moisture Content (%)	14.0	15.5	16.0		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	101.5	101.5	101.5		
Moisture Variation (%)	0.0	0.5 wet	0.5 wet		
Hilf Density Ratio (%)	99.5	101.0	101.5		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00011

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: Iac-MRA **NATA**

Accreditation Number:

12719

Approved Signatory: M. Longfield

(Senior Technician) Site Number: 12712 Date of Issue: 10/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95%

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Sample Data					
Sample ID	S23DS-00029	S23DS-00030	S23DS-00031	S23DS-00032	
Field Sample ID	1	2	3	4	
Date Tested	6/01/2023	6/01/2023	6/01/2023	6/01/2023	
Time Tested	11:30	11:40			
E:	356425	356461	356436	356462	
N:	5781204	5781190	5781215	5781194	
EL:	43.56	42.36	43.60	42.73	
Lot / Layer:	4207 / 1	4211 / 1	4208 / 2	4211 / 2	
Field and Laboratory Data					
Depth of Test (mm)	175	175	175	175	
Depth of Layer (mm)	200	200	200	200	
AS Sieve Size (mm)	19.0	19.0	19.0	19.0	
Oversize Wet (%)	0	0	0	0	
Field Moisture Content (%)	13.1	13.8	13.6	15.6	
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	
Field Wet Density (t/m³)	2.20	2.16	2.08	2.04	
Field Dry Density (t/m³)	1.94	1.90	1.83	1.76	
Peak Converted Wet Density (t/m³)	2.18	2.14	2.14	2.06	
Optimum Moisture Content (%)	13.0	14.0	14.0	16.5	
Compactive Effort	Standard	Standard	Standard	Standard	
Moisture Ratio (%)	103.0	97.5	96.5	95.5	
Moisture Variation (%)	0.5 wet	0.5 dry	0.5 dry	0.5 dry	
Hilf Density Ratio (%)	101.0	101.0	97.0	98.5	





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00015

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

ATA

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Site Number: 12712 Date of Issue: 10/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Sandy Clay

Sample Data				
Sample ID	S23DS-00043	S23DS-00044		
Field Sample ID	1	2		
Date Tested	7/01/2023	7/01/2023		
Time Tested	10:30	10:40		
E:	356465	356479		
N:	5781194	5781195		
RL:	42.70	42.13		
Lot / Layer:	4211 / 3	4210 / 3		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	13.7	13.4		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.14	2.14		
Field Dry Density (t/m³)	1.88	1.88		
Peak Converted Wet Density (t/m³)	2.07	2.09		
Optimum Moisture Content (%)	16.0	15.5		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	86.5	86.5		
Moisture Variation (%)	2.0 dry	2.0 dry		
Hilf Density Ratio (%)	103.5	102.5		

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00024

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA **NATA**

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

12719 Site Number: 12712 Date of Issue: 17/05/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data					
Sample ID	S23DS-00075	S23DS-00076	S23DS-00077		
Field Sample ID	1	2	3		
Date Tested	9/01/2023	9/01/2023	9/01/2023		
Time Tested	11:30	11:45	14:50		
E:	356416	356461	356461		
N:	5781223	5781206	5781192		
RL:	43.99	42.90	43.16		
Lot / Layer:	4208 / 4	4210 / 4	4211 / 5		
Field and Laboratory Data					
Depth of Test (mm)	175	175	175		
Depth of Layer (mm)	200	200	200		
AS Sieve Size (mm)	19.0	19.0	19.0		
Oversize Wet (%)	0	0	0		
Field Moisture Content (%)	10.5	14.0	12.4		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.15	2.14	2.07		
Field Dry Density (t/m³)	1.95	1.88	1.84		
Peak Converted Wet Density (t/m³)	2.13	2.13	2.09		
Optimum Moisture Content (%)	12.5	14.5	15.0		
Compactive Effort	Standard	Standard	Standard		
Moisture Ratio (%)	83.5	97.5	82.5		
Moisture Variation (%)	2.0 dry	0.5 dry	2.5 dry		
Hilf Density Ratio (%)	101.0	100.0	99.0		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00034

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician)

Site Number: 12712 Date of Issue: 20/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S23DS-00113	S23DS-00114		
Field Sample ID	1	2		
Date Tested	10/01/2023	10/01/2023		
Time Tested	10:30	15:10		
E:	356471	356475		
N:	5781206	5781188		
RL:	42.96	43.12		
Lot / Layer:	4210 / 5	4211 / 6		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	14.8	18.4		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.16	2.17		
Field Dry Density (t/m³)	1.88	1.83		
Peak Converted Wet Density (t/m³)	2.09	2.08		
Optimum Moisture Content (%)	16.5	20.5		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	90.0	90.5		
Moisture Variation (%)	1.5 dry	2.0 dry		
Hilf Density Ratio (%)	103.5	104.0		

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00083

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 20/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data	Sample Data								
Sample ID	S23DS-00261								
Field Sample ID	1								
Date Tested	13/01/2023								
Time Tested	09:16								
E:	356446								
N:	5781039								
RL:	39.42								
Lot / Layer:	4222 / -								
Field and Laboratory Data									
Depth of Test (mm)	175								
Depth of Layer (mm)	200								
AS Sieve Size (mm)	19.0								
Field Moisture Content (%)	14.5								
Field Moisture Content Method	AS 1289.2.1.1								
Field Wet Density (t/m³)	2.08								
Field Dry Density (t/m³)	1.81								
Peak Converted Wet Density (t/m³)	2.04								
Optimum Moisture Content (%)	17.0								
Compactive Effort	Standard								
Moisture Ratio (%)	86.0								
Moisture Variation (%)	2.5 dry								
Hilf Density Ratio (%)	101.5								





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00171

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project: Meridian Estate, Stage

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 3/02/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Sandy Clay

Sample Data				
Sample ID	S23DS-00550			
Field Sample ID	1			
Date Tested	24/01/2023			
Time Tested	14:23			
E:	2605.097 (356426)			
N:	389.846 (5781236)			
EL:	44.209			
Lot / Layer:	4209 / -			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	12.0			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.15			
Field Dry Density (t/m³)	1.92			
Peak Converted Wet Density (t/m³)	2.16			
Optimum Moisture Content (%)	12.5			
Compactive Effort	Standard			
Moisture Ratio (%)	96.5			
Moisture Variation (%)	0.5 dry			
Hilf Density Ratio (%)	99.5			

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00514

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

NATA

Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 3/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Sandy Clay / Silt

Sample Data	Sample Data								
Sample ID	S23DS-01694	S23DS-01695	S23DS-01696	S23DS-01697					
Field Sample ID	1	2	3	4					
Date Tested	24/02/2023	24/02/2023	24/02/2023	24/02/2023					
Time Tested	12:47	12:56	13:07	14:07					
E:	2645.794 (356470)	2648.851 (356473)	2650.897 (356475)	- (356476)					
N:	257.407 (5781102)	284.436 (5781128)	314.798 (5781157)	- (5781208)					
EL:	41.220	41.769	42.609	-					
Lot / Layer:	4217 / 7	4215 / 8	8	4210 / 7					
Field and Laboratory Data									
Depth of Test (mm)	175	175	175	175					
Depth of Layer (mm)	200	200	200	200					
AS Sieve Size (mm)	19.0	19.0	19.0	19.0					
Oversize Wet (%)	0	0	0	0					
Field Moisture Content (%)	13.1	19.6	18.1	15.0					
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1	AS 1289.2.1.1					
Field Wet Density (t/m³)	2.09	2.05	2.08	1.93					
Field Dry Density (t/m³)	1.85	1.72	1.76	1.68					
Peak Converted Wet Density (t/m³)	2.14	2.06	2.00	2.03					
Optimum Moisture Content (%)	13.5	19.5	20.0	17.5					
Compactive Effort	Standard	Standard	Standard	Standard					
Moisture Ratio (%)	96.5	101.5	90.5	85.0					
Moisture Variation (%)	0.5 dry	0.5 wet	2.0 dry	2.5 dry					
Hilf Density Ratio (%)	97.5	99.5	104.0	94.5					





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00537

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Site Number: 12712 | Date of Issue: 3/03/2023

Site Number: 12712 Date of Issue: 3/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Sandy Clay, traces of Gravel

Sample Data	Sample Data							
Sample ID	S23DS-01757							
Field Sample ID	1							
Date Tested	27/02/2023							
Time Tested	12:10							
E:	2652.379							
N:	364.796							
EL:	43.103							
Lot / Layer:	4210 / 7							
	Retest of S23DS-01697							
Field and Laboratory Data								
Depth of Test (mm)	175							
Depth of Layer (mm)	200							
AS Sieve Size (mm)	19.0							
Oversize Wet (%)	0							
Field Wet Density (t/m³)	1.97							
Peak Converted Wet Density (t/m³)	1.98							
Compactive Effort	Standard							
Moisture Variation (%)	4.0 dry							
Hilf Density Ratio (%)	99.5							

\mathbf{c}	m	m	01	+-
Cc)	ш	ei	เเธ





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00579

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

TA

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

Site Number: 12712 Date of Issue: 3/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Silty Clay

Sample Data				
Sample ID	S23DS-01863			
Field Sample ID	1			
Date Tested	1/03/2023			
Time Tested	12:35			
Lot / Layer:	4210 / 7			
	Retest of S23DS-01757			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	14.2			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.06			
Field Dry Density (t/m³)	1.81			
Peak Converted Wet Density (t/m³)	2.17			
Optimum Moisture Content (%)	14.0			
Compactive Effort	Standard			
Moisture Ratio (%)	100.0			
Moisture Variation (%)	0.0			
Hilf Density Ratio (%)	95.0			





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00604

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA **NATA**

Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 20/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S23DS-01959			
Field Sample ID	1			
Date Tested	2/03/2023			
Time Tested	14:15			
E;	2642.794 (356468)			
N:	226.968 (5781065)			
EL:	40.349			
Lot / Layer:	4219 / 7			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	14.2			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.12			
Field Dry Density (t/m³)	1.85			
Peak Converted Wet Density (t/m³)	2.16			
Optimum Moisture Content (%)	14.5			
Compactive Effort	Standard			
Moisture Ratio (%)	98.5			
Moisture Variation (%)	0.0			
Hilf Density Ratio (%)	98.0			

\sim	-	-		-1-
Co	144	144	T 🖴	116
\sim	ш	ш		





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00617

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

IC MRA NATA

Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 20/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite
Material: Silty Clay

Sample Data				
Sample ID	S23DS-01988			
Field Sample ID	1			
Date Tested	3/03/2023			
Time Tested	12:38			
E:	2638.690 (356461)			
N:	211.681 (5781051)			
EL:	40.15			
Lot / Layer:	4220 / 8			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	16.5			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.13			
Field Dry Density (t/m³)	1.83			
Peak Converted Wet Density (t/m³)	2.11			
Optimum Moisture Content (%)	16.5			
Compactive Effort	Standard			
Moisture Ratio (%)	101.0			
Moisture Variation (%)	0.0			
Hilf Density Ratio (%)	101.0			

C	_	100	m	_	nto
	U	ш	ш	е	nts





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00619

Issue No: 1

HILF Density Ratio Report

Greenridge Properties Pty Ltd Client:

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA **NATA**

Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician) Site Number: 12712 Date of Issue: 20/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Silty Clay

Sample Data				
Sample ID	S23DS-01989	S23DS-01990		
Field Sample ID	1	2		
Date Tested	4/03/2023	4/03/2023		
Time Tested	11:03	11:16		
E:	2654.503 (356478)	2642.647 (356467)		
N:	348.586 (5781193)	375.773 (5781221)		
EL:	43.178	43.367		
Lot / Layer:	4211 / 8	4210 / 9		
Field and Laboratory Data				
Depth of Test (mm)	175	175		
Depth of Layer (mm)	200	200		
AS Sieve Size (mm)	19.0	19.0		
Oversize Wet (%)	0	0		
Field Moisture Content (%)	12.3	13.2		
Field Moisture Content Method	AS 1289.2.1.1	AS 1289.2.1.1		
Field Wet Density (t/m³)	2.01	2.09		
Field Dry Density (t/m³)	1.79	1.85		
Peak Converted Wet Density (t/m³)	2.02	2.15		
Optimum Moisture Content (%)	16.0	13.5		
Compactive Effort	Standard	Standard		
Moisture Ratio (%)	76.0	98.5		
Moisture Variation (%)	4.0 dry	0.0		
Hilf Density Ratio (%)	99.5	97.0		





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00650

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 20/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite Material: Sandy Clay

Cample Date				
Sample Data				
Sample ID	S23DS-02103			
Field Sample ID	1			
Date Tested	7/03/2023			
Time Tested	07:39			
Lot / Layer:	4211 / 8			
	Retest of S23DS-01989			
Field and Laboratory Data				
Depth of Test (mm)	175			
Depth of Layer (mm)	200			
AS Sieve Size (mm)	19.0			
Oversize Wet (%)	0			
Field Moisture Content (%)	14.1			
Field Moisture Content Method	AS 1289.2.1.1			
Field Wet Density (t/m³)	2.11			
Field Dry Density (t/m³)	1.85			
Peak Converted Wet Density (t/m³)	2.07			
Optimum Moisture Content (%)	16.5			
Compactive Effort	Standard			
Moisture Ratio (%)	85.0			
Moisture Variation (%)	2.5 dry			_
Hilf Density Ratio (%)	102.0			





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: HDR:W23DS00742

Accredited for compliance with ISO/IEC 17025

Issue No: 1

HILF Density Ratio Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:

Iac MRA NAT

NATA

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician)
Site Number: 12712 Date of Issue: 20/03/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Location:

Client Request ID:

Specification Requirements: Minimum Hilf Density Ratio of 95% (+- 3% of OMC)

Field Test procedures: AS 1289.5.8.1

Laboratory Test procedures: AS 1289.2.1.1, AS 1289.5.7.1 Sampling Method: AS1289.1.2.1 Clause 6.4 (b)

Source: Onsite

Material: Silty Clay, traces of Gravel

Sample Data	Sample Data							
Sample ID	S23DS-02361	S23DS-02362						
Field Sample ID	1	2						
Date Tested	16/03/2023	16/03/2023						
Time Tested	15:30	15:38						
E:	2621.798 (356446)	264.807 (356465)						
N:	198.007 (5781041)	14.435 (5781038)						
EL:	39.917	39.475						
Lot / Layer:	4221 / 4	4223 / 4						
Field and Laboratory Data								
Depth of Test (mm)	175	175						
Depth of Layer (mm)	200	200						
AS Sieve Size (mm)	19.0	19.0						
Oversize Wet (%)	0	0						
Field Wet Density (t/m³)	2.04	2.14						
Peak Converted Wet Density (t/m³)	2.06	2.09						
Compactive Effort	Standard	Standard						
Moisture Variation (%)	2.5 dry	2.0 dry						
Hilf Density Ratio (%)	99.0	102.5						

\mathbf{c}	m	m	01	+-
Cc)	ш	ei	เเธ





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S22DS-08310/1

Issue No: 1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: Iac-MRA

Accreditation Number:



Accredited for compliance with ISO/IEC 17025

Approved Signatory: J. Lamont (Dandenong Laboratory Manager)

Limits

12719 Site Number: 12712 Date of Issue: 11/11/2022 THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Sample Location E 245.014, N 2598.869, EL: 41.46, Lot 4233

Field Sample ID

Date Sampled 19/10/2022 Source Onsite

Material CH CLAY with sand trace gravel

Specification **AS** Grading

Sampling Method AS1289.1.2.1 Clause 6.4 (b)

S22DS-08310 Sample ID

Particle Size Distribution

AS 1289.3.6.1 Method: Drying By: Oven Date Tested: 24/10/2022


Note: Sample Washed

Sieve Size	% Passing
19.0mm	100
13.2mm	99
9.5mm	99
6.7mm	97
4.75mm	95
2.36mm	92
1.18mm	90
600µm	87
425µm	84
300µm	80
150µm	67
75µm	63

Other Test Results

Description	Method	Result	Limits
Moisture Content (%)	AS 1289.2.1.1	21.6	
Sample History	AS 1289.1.1 O	ven-dried	
Preparation	AS 1289.1.1 D	ry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	20.5	
Mould Length (mm)		250	
Crumbling		No	
Curling		No	
Cracking		Yes	
Liquid Limit (%)	AS 1289.3.1.2	54	
Plastic Limit (%)	AS 1289.3.2.1	22	
Plasticity Index (%)	AS 1289.3.3.1	32	
Date Tested	25	5/10/2022	

Chart



Comments



Project:



Dandenong South ACN 143 009 330

25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S22DS-08769/1

Issue No: 1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123 Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.:





Accredited for compliance with ISO/IEC 17025

Limits

Approved Signatory: M. Longfield

Accreditation Number: 12719 (Senior Technician)

Site Number: 12712 Date of Issue: 17/11/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Sample Location

Field Sample ID

Date Sampled 8/11/2022 **Time Sampled** 07:25 Source Onsite Material Silty Clay Specification AS Grading

AS1289.1.2.1 Clause 6.4 (b) Sampling Method

Sample ID S22DS-08769

Particle Size Distribution

AS 1289.3.6.1 Method:

Drying By: Oven **Date Tested: 9/11/2022**


Note: Sample Washed

ı	Sieve Size	% Passing
ı	19.0mm	100
ı	13.2mm	100
ı	9.5mm	98
ı	6.7mm	96
ı	4.75mm	94
ı	2.36mm	91
	1.18mm	88
ı	600µm	83
1	425µm	79
1	300µm	72
ı	150µm	50
ı	75µm	43

Other Test Results

Description	Method	Result	Limits	
Moisture Content (%)	AS 1289.2.1.1	14.6		
Sample History	AS 1289.1.1 Ov	en-dried		
Preparation	AS 1289.1.1 Dr	y Sieved		
Linear Shrinkage (%)	AS 1289.3.4.1	11.0		
Mould Length (mm)		250		
Crumbling		No		
Curling		Yes		
Cracking		No		
Liquid Limit (%)	AS 1289.3.1.2	38		
Plastic Limit (%)	AS 1289.3.2.1	13		
Plasticity Index (%)	AS 1289.3.3.1	25		
Date Tested	11,	/11/2022		
	Moisture Content (%) Sample History Preparation Linear Shrinkage (%) Mould Length (mm) Crumbling Curling Curling Cracking Liquid Limit (%) Plastic Limit (%) Plasticity Index (%)	Moisture Content (%) Sample History Preparation Linear Shrinkage (%) Mould Length (mm) Crumbling Curling Cracking Liquid Limit (%) Plastic Limit (%) Plasticity Index (%) AS 1289.2.1.1 AS 1289.1.1 AS 1289.3.4.1 AS 1289.3.4.1 AS 1289.3.2.1 AS 1289.3.3.1	Moisture Content (%) AS 1289.2.1.1 14.6 Sample History AS 1289.1.1 Oven-dried Preparation AS 1289.1.1 Dry Sieved Linear Shrinkage (%) AS 1289.3.4.1 11.0 Mould Length (mm) 250 Crumbling No Curling Yes Cracking No Liquid Limit (%) AS 1289.3.1.2 38 Plastic Limit (%) AS 1289.3.2.1 13 Plasticity Index (%) AS 1289.3.3.1 25	Moisture Content (%) AS 1289.2.1.1 14.6 Sample History AS 1289.1.1 Oven-dried Preparation AS 1289.1.1 Dry Sieved Linear Shrinkage (%) AS 1289.3.4.1 11.0 Mould Length (mm) 250 Crumbling No Curling Yes Cracking No Liquid Limit (%) AS 1289.3.1.2 38 Plastic Limit (%) AS 1289.3.2.1 13 Plasticity Index (%) AS 1289.3.3.1 25

Chart



Comments





25 Metcalf Street
DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S22DS-09640/1

Issue No: 1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: CG Request No.:

TRN: Lot No.:



Accreditation Number:

12719



Accredited for compliance with ISO/IEC 17025 – Testing

Approved Signatory: J. Lamont (Dandenong Laboratory Manager) Date of Issue: 12/12/2022

Limits

Site Number: 12712 Date of Issue: 12/12/2022
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

0/ Deceine

Sample Details

Sample Location E 356451, N 5781142, Layer 3

Field Sample ID

Date Sampled 1/12/2022 Source Onsite

Material CH; CLAY with sand trace gravel, red, high plasticity.

Specification AS Grading

Sampling Method AS1289.1.2.1 Clause 6.4 (b)

Sample ID S22DS-09640

Particle Size Distribution

Method: AS 1289.3.6.1 Drying By: Oven

Date Tested: 6/12/2022

Ciava Ciaa


Note: Sample Washed

Sieve Size	% Passing
26.5mm	100
19.0mm	99
13.2mm	99
9.5mm	98
6.7mm	97
4.75mm	96
2.36mm	93
1.18mm	91
600µm	89
425µm	87
300µm	84
150µm	74
75µm	71

Other Test Results

Description	Method	Result	Limits
Moisture Content (%)	AS 1289.2.1.1	24.3	
Sample History	AS 1289.1.1 (Oven-dried	
Preparation	AS 1289.1.1 [Ory Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	17.5	
Mould Length (mm)		250	
Crumbling		No	
Curling		Yes	
Cracking		No	
Liquid Limit (%)	AS 1289.3.1.2	72	
Plastic Limit (%)	AS 1289.3.2.1	20	
Plasticity Index (%)	AS 1289.3.3.1	52	
Date Tested		6/12/2022	

Chart



Comments





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S23DS-00028/1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: lac-MRA



Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician)

Site Number: 12712 Date of Issue: 23/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Sample Location Field Sample ID

Date Sampled

Source Onsite Material Clay **Specification** AS Grading

Particle Size Distribution

Sampling Method

Sample ID S23DS-00028

Other Test Results			
Description	Method	Result	Limits
Moisture Content (%)	AS 1289.2.1.1	14.6	
Sample History	AS 1289.1.1	Oven-dried	
Preparation	AS 1289.1.1	Dry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	7.5	
Mould Length (mm)		250	
Crumbling		No	

% Passing 70 50 30

Sieve

Drying By: Oven

AS 1289.3.6.1

Date Tested: 16/01/2023

Note: Sample Wa	shed	
Sieve Size	% Passing	Limits
19.0mm	100	
13.2mm	100	
9.5mm	98	
6.7mm	95	
4.75mm	93	
2.36mm	91	
1.18mm	88	
600µm	83	
425µm	79	
300µm	72	
150µm	49	
75µm	42	
•		

Comments





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S23DS-00028/1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.:



NATA

Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield 12719 (Senior Technician)

Site Number: 12712 Date of Issue: 23/01/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Description	Method	Result	Limits
Curling		Yes	
Cracking		No	
Liquid Limit (%)	AS 1289.3.1.2	30	
Plastic Limit (%)	AS 1289.3.2.1	12	
Plasticity Index (%)	AS 1289.3.3.1	18	
Date Tested		17/01/2023	

Comments





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S23DS-00115/1

Issue No: 1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.: Iac-MRA



Accredited for compliance with ISO/IEC 17025

Accreditation Number: Approved Signatory: M. Longfield

12719 (Senior Technician) Site Number: 12712 Date of Issue: 3/02/2023 THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Sample Details

Sample Location E: 356475, N: 5781188, RL: 43.12, Lot: 4211, Layer: 1

Field Sample ID


10/01/2023 **Date Sampled** Source Onsite Material Silty Clay **Specification** AS Grading

Sampling Method AS1289.1.2.1 Clause 6.4 (b)

Sample ID S23DS-00115

Other Test Results			
Description	Method	Result	Limits
Moisture Content (%)	AS 1289.2.1.1	14.9	
Sample History	AS 1289.1.1	Oven-dried	
Preparation	AS 1289.1.1	Dry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	7.5	
Mould Length (mm)		250	
Crumbling		No	

Particle Size Distribution



AS 1289.3.6.1

Drying By: Oven

Date Tested: 16/01/2023

Note: Sample Washed Limits % Passing Sieve Size 19.0mm 96 13.2mm 9.5mm 93 6.7mm 90 4.75mm 87 2.36mm 83 1.18mm 79 600µm 75 425µm 72 300µm 66 150µm 48 75µm 43

Comments





25 Metcalf Street DANDENONG SOUTH, VIC 3175

Ph: +61 3 8796 7900 Fax: +61 3 9706 9431

Report No: MAT:S23DS-00115/1

Material Test Report

Client: Greenridge Properties Pty Ltd

Address: PO Box 3131

AUBURN VIC 3123

Project: Meridian Estate, Stage 42

Project No.: 3807351.042

Order No.: **CG Request No.:**

TRN: Lot No.:





Accredited for compliance with ISO/IEC 17025 – Testing

Accreditation Number: Approved Signatory: M. Longfield (Senior Technician)

12719 Site Number: 12712 Date of Issue: 3/02/2023
THIS DOCUMENT SHALL NOT BE REPRODUCED EXCEPT IN FULL

Description	Method	Result	Limits
Curling		No	
Cracking		No	
Liquid Limit (%)	AS 1289.3.1.2	35	
Plastic Limit (%)	AS 1289.3.2.1	15	
Plasticity Index (%)	AS 1289.3.3.1	20	
Date Tested		20/01/2023	

\sim	m	m	\sim	nto
C U	200	ш	e	nts

Appendix D: Controlled Fill Certificate



CONTROLLED FILL CERTIFICATE - LEVEL 1 INSPECTION & TESTING

PROJECT: Meridian Central Estate Stage 42

Lots 4201 to 4234

Chadwick Geotechnics REF: 3807351.042v1

DATE: 16 May 2023

CLIENT: Greenridge Properties Pty Ltd

PO Box 4136

Dandenong South VIC 3164

SUMMARY

Chadwick Geotechnics Pty Ltd conducted, Level 1 inspection and testing, in accordance with Section 8.2 Level 1 inspection and Testing AS3798-2007, Guidelines on earthworks for commercial and residential developments, during the filling of the site.

So far as can be determined, the fill was placed in accordance with the Specification that required a minimum density ratio of 95% of HILF Density (AS1289.5.7.1) to be achieved.

LIMITATIONS

This Certificate has been commissioned for the filling of the area mentioned above. No responsibility or liability will be accepted for the use of this report for any purpose other than that for which Chadwick Geotechnics Pty Ltd was engaged, specifically for Level 1 Inspection and Testing of the structural fill (excluding topsoil).

This report is based on the conditions present and factors affecting the soil at the time of inspection (7 September 2022 and was completed on 16 March 2023). No responsibility or liability will be accepted and Chadwick Geotechnics Pty Ltd is indemnified to the full extent permitted by law in respect of the use of this Certificate where there has been a change in the nature of the project, or in the site conditions since the site testing.

CHADWICK GEOTECHNICS PTY LTD

Rober Border

Robert Barden Project Manager Timothy Chadwick Project Director

© Chadwick Geotechnics Pty Ltd.

No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying or otherwise other than in accordance with the limitations and for the purpose provided for above.

www.chadwickgeotechnics.com.au



